

QUANTITY SHEET 1

SUMMARY OF ESTIMATED QUANTITIES										TOTALS		DESCRIPTIONS				DETAILED SUMMARY OF QUANTITIES			
								EROSION CONTROL	BRIDGE	ROADWAY	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	ROUND	QUANTITIES	UNIT	ITEMS
										25	25		CY	COMMON EXCAVATION	203.15				
									105		105		CY	UNCLASSIFIED CHANNEL EXCAVATION	203.27				
									500		500		CY	STRUCTURE EXCAVATION	204.25				
									270		270		CY	GRANULAR BACKFILL FOR STRUCTURES	204.30				
										50	50		TON	SUBBASE OF CRUSHED GRAVEL, FINE GRADED	301.28				
										50	50		TON	SUPERPAVE BITUMINOUS CONCRETE PAVEMENT	490.30				
									1		1		EACH	REMOVAL OF STRUCTURE (5'-9" x 8'-2" CGMPPA)	529.15				
									1		1		LS	PRECAST CONCRETE STRUCTURE (14'-0" x 8'-0" x 52'-6" BOX)	540.10				
							1				1		MGAL	DUST CONTROL WITH WATER	609.10				
									70		70		CY	STONE FILL, TYPE III	613.12				
										500	500		HR	FLAGGERS	630.15				
										75	75		SY	GEOTEXTILE UNDER STONE FILL	649.31				
							130				130		SY	GEOTEXTILE FOR SILT FENCE	649.51				
							45				45		SY	GEOTEXTILE FOR FILTER CURTAIN	649.61				
							7				7		LB	SEED	651.15				
							7				7		LB	SEED, WINTER RYE	651.17				
							50				50		LB	FERTILIZER	651.18				
							1				1		TON	AGRICULTURAL LIMESTONE	651.20				
							1				1		TON	HAY MULCH	651.25				
							65				65		CY	TOPSOIL	651.35				
									40		40		SY	GRUBBING MATERIAL	651.40				
							1				1		LS	EPSC PLAN (BF 013-1(22))	652.10				
							40				40		HR	MONITORING EPSC PLAN	652.20				
							1				1		LU	MAINTENANCE OF EPSC PLAN (N.A.B.I.) (BF 013-1(22))	652.30				
							570				570		SY	TEMPORARY EROSION MATTING	653.20				
							60				60		CY	VEHICLE TRACKING PAD	653.35				
							1				1		EACH	FILTER BAG	653.45				
							300				300		LF	PROJECT DEMARCATION FENCE	653.55				
									90		90		CY	SPECIAL PROVISION (STONE FILL, STREAM BED MATERIAL)	900.608				
										1	1		LS	SPECIAL PROVISION (CPM SCHEDULE)(BF 013-1(22))	900.645				
									1		1		LS	SPECIAL PROVISION (TEMPORARY RELOCATION OF STREAM)(BF 013-1(22))	900.645				
										1	1		LS	SPECIAL PROVISION (TRAFFIC CONTROL, ALL-INCLUSIVE)(BF 013-1(22))	900.645				
										1	1		LU	SPECIAL PROVISION (INCENTIVE/DISINCENTIVE)(N.A.B.I.)(BF 013-1(22))	900.650				

PROJECT NAME: WARDBORO
 PROJECT NUMBER: BF 013-1(22)
 FILE NAME: sl3b074qs.dgn
 PROJECT LEADER: K. HIGGINS
 DESIGNED BY: J. SALVATORI
 QUANTITY SHEET
 PLOT DATE: 26-FEB-2014
 DRAWN BY: J. SALVATORI
 CHECKED BY: G. LAROCHE
 SHEET 427 OF 444