

QUANTITY SHEET 1

SUMMARY OF ESTIMATED QUANTITIES										TOTALS		DESCRIPTIONS				DETAILED SUMMARY OF QUANTITIES			
					ROADWAY	EROSION CONTROL	RAILROAD	CULVERT # 73A	CULVERT # CO6470	FULL C.E. ITEMS	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	ROUND	QUANTITIES	UNIT	ITEMS
					1						1		LS	CLEARING AND GRUBBING, INCLUDING INDIVIDUAL TREES AND STUMPS	201.10	-			
					510		230				740		CY	COMMON EXCAVATION	203.15	-			
								140	180		320		CY	UNCLASSIFIED CHANNEL EXCAVATION	203.27	-			
					110						110		CY	TRENCH EXCAVATION OF EARTH	204.20	-			
					1						1		CY	TRENCH EXCAVATION OF EARTH, EXPLORATORY (N.A.B.I.)	204.22	-			
								600	400		1000		CY	STRUCTURE EXCAVATION	204.25	-			
								400	240		640		CY	GRANULAR BACKFILL FOR STRUCTURES	204.30	-			
					320						320		SY	COLD PLANING, BITUMINOUS PAVEMENT	210.10	-			
					410						410		CY	SUBBASE OF CRUSHED GRAVEL, COARSE GRADED	301.25	-			
							90				90		CY	SUBBASE OF CRUSHED GRAVEL, FINE GRADED	301.26	-			
					8						8		CWT	EMULSIFIED ASPHALT	404.65	-			
					1						1		LU	PRICE ADJUSTMENT, ASPHALT CEMENT (N.A.B.I.)	406.50	-			
								2	2		4		GAL	WATER REPELLENT, SILANE	514.10	-			
									1		1		LS	PRECAST CONCRETE STRUCTURE (8' X 6' X 37' BOX)	540.10	-			
								1			1		LS	PRECAST CONCRETE STRUCTURE (8' X 6' X 60' BOX)	540.10	-			
								270	160		430		CY	STONE FILL, TYPE III	613.12	-			
					102						102		LF	STEEL BEAM GUARDRAIL, GALVANIZED	621.20	-			
					174						174		LF	STEEL BEAM GUARDRAIL, GALVANIZED/NESTED	621.206	-			
					2						2		EACH	MANUFACTURED TERMINAL SECTION, FLARED	621.50	-			
					1						1		EACH	ANCHOR FOR STEEL BEAM RAIL	621.60	-			
					81						81		LF	REMOVAL AND DISPOSAL OF GUARDRAIL	621.80	-			
								60	70		130		TON	CRUSHED STONE BEDDING	629.54	-			
					10						10		HR	UNIFORMED TRAFFIC OFFICERS	630.10	-			
					80						80		HR	FLAGGERS	630.15	-			
										1	1		LS	FIELD OFFICE, ENGINEERS	631.10	-			
										1	1		LS	TESTING EQUIPMENT, BITUMINOUS	631.17	-			
										3000	3000		DL	FIELD OFFICE TELEPHONE (N.A.B.I.)	631.26	-			
					1						1		LS	MOBILIZATION/DEMOBILIZATION	635.11	-			
					900						900		LF	DURABLE 4 INCH WHITE LINE	646.400	-			
					900						900		LF	DURABLE 4 INCH YELLOW LINE	646.410	-			
					500						500		LF	TEMPORARY 4 INCH WHITE LINE	646.600	-			
					500						500		LF	TEMPORARY 4 INCH YELLOW LINE	646.610	-			
					300		180				480		SY	GEOTEXTILE FOR ROADBED SEPARATOR	649.11	-			
							260				260		SY	GEOTEXTILE UNDER RAILROAD BALLAST	649.21	-			
								510	320		830		SY	GEOTEXTILE UNDER STONE FILL	649.31	-			
						65					65		SY	GEOTEXTILE FOR SILT FENCE	649.51	-			
						16					16		LB	SEED	651.15	-			
						130					130		LB	FERTILIZER	651.18	-			
						1					1		TON	AGRICULTURAL LIMESTONE	651.20	-			
						1					1		TON	HAY MULCH	651.25	-			

PROJECT NAME: WALLINGFORD
PROJECT NUMBER: ER CULV(39)
FILE NAME: z12b380_frm.dgn PLOT DATE: 7/14/2016
PROJECT LEADER: G. BOGUE DRAWN BY: I. MAYNARD
DESIGNED BY: I. MAYNARD CHECKED BY: T. KNIGHT
QUANTITY SHEET 1 SHEET 5 OF 36