

# QUANTITY SHEET 2

SUMMARY OF ESTIMATED QUANTITIES										TOTALS		DESCRIPTIONS				DETAILED SUMMARY OF QUANTITIES		
				ROADWAY	EROSION CONTROL	RAILROAD	CULVERT # 73A	CULVERT # CO6470	FULL C.E. ITEMS	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	ROUND	QUANTITIES	UNIT	ITEMS
					80					80		CY	TOPSOIL	651.35	-			
					610					610		SY	GRUBBING MATERIAL	651.40	-			
					1					1		LS	EPSC PLAN	652.10	-			
					40					40		HR	MONITORING EPSC PLAN	652.20	-			
					1					1		LU	MAINTENANCE OF EPSC PLAN (N.A.B.I.)	652.30	-			
					495					495		SY	TEMPORARY EROSION MATTING	653.20	-			
					20					20		CY	TEMPORARY STONE CHECK DAM, TYPE I	653.25	-			
					60					60		CY	VEHICLE TRACKING PAD	653.35	-			
					2					2		EACH	FILTER BAG	653.45	-			
					280					280		LF	BARRIER FENCE	653.50	-			
					280					280		LF	PROJECT DEMARCATION FENCE	653.55	-			
				1						1		SF	TRAFFIC SIGNS, TYPE A	675.20	0.16			
				16						16		LF	SQUARE TUBE SIGN POST AND ANCHOR	675.341	-			
						90				90		CY	SPECIAL PROVISION (RAILROAD BALLAST)	900.608	-			
							50	65		115		CY	SPECIAL PROVISION (STONE FILL, STREAM BED MATERIAL)(TYPE I)	900.608	-			
						50				50		EACH	SPECIAL PROVISION (REMOVAL AND REPLACEMENT OF CROSS TIES)	900.620	-			
				1						1		EACH	SPECIAL PROVISION (TEMPORARY TRAFFIC SIGNAL SYSTEM, PORTABLE)	900.620	-			
						100				100		LF	SPECIAL PROVISION (REMOVE AND RESET RAILROAD TRACKS)	900.640	-			
							1			1		LS	SPECIAL PROVISION (TEMPORARY RELOCATION OF STREAM)(CULVERT 73A)	900.645	-			
								1		1		LS	SPECIAL PROVISION (TEMPORARY RELOCATION OF STREAM)(CULVERT CO6470)	900.645	-			
				1						1		LS	SPECIAL PROVISION (TRAFFIC CONTROL, ALL-INCLUSIVE)	900.645	-			
						1				1		LU	SPECIAL PROVISION (MAINTENANCE OF RAILROAD TRAFFIC)(N.A.B.I.)	900.650	-			
				1						1		LU	SPECIAL PROVISION (MAT DENSITY PAY ADJUSTMENT, SMALL QUANTITY)(N.A.B.I.)	900.650	-			
				1						1		LU	SPECIAL PROVISION (MIXTURE PAY ADJUSTMENT)(N.A.B.I.)	900.650	-			
				290						290		TON	SPECIAL PROVISION (BITUMINOUS CONCRETE PAVEMENT, SMALL QUANTITY)	900.680	-			

PROJECT NAME:	WALLINGFORD
PROJECT NUMBER:	ER CULV(39)
FILE NAME: z12b380_frm.dgn	PLOT DATE: 6/16/2016
PROJECT LEADER: G. BOGUE	DRAWN BY: I. MAYNARD
DESIGNED BY: I. MAYNARD	CHECKED BY: T. KNIGHT
QUANTITY SHEET 2	SHEET 6 OF 36