

QUANTITY SHEET 1

SUMMARY OF ESTIMATED QUANTITIES										TOTALS		DESCRIPTIONS				DETAILED SUMMARY OF QUANTITIES		
							ROADWAY	EROSION CONTROL	FULL C.E. ITEMS	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	ROUND	QUANTITIES	UNIT	ITEMS
							1			1		LS	CLEARING AND GRUBBING, INCLUDING INDIVIDUAL TREES AND STUMPS	201.10	-	UNCLASSIFIED EXCAVATION		
							6000			6000		CY	UNCLASSIFIED EXCAVATION	203.17	62	5938 CY		CHANNEL
							11000			11000		CY	UNCLASSIFIED CHANNEL EXCAVATION	203.27	242	62 CY		ROUNDING
							1			1		CY	TRENCH EXCAVATION OF EARTH, EXPLORATORY (N.A.B.I.)	204.22	-	6000 CY		TOTAL
							1200			1200		CY	SUBBASE OF DENSE GRADED CRUSHED STONE	301.35	101	UNCLASSIFIED CHANNEL EXCAVATION		
							40			40		CY	AGGREGATE SHOULDERS, IN PLACE	402.10	9	10758 CY		CHANNEL
							20			20		LF	24" PCCSP .064 (2-2/3 X 1/2)	601.0425	8	242 CY		ROUNDING
							20			20		LF	30" PCCSP .079 (2-2/3 X 1/2)	601.0436	10	11000 CY		TOTAL
							75			75		MGAL	DUST CONTROL WITH WATER	609.10	1	SUBBASE OF DENSE GRADED CRUSHED STONE		
								1400		1400		CY	STONE FILL, TYPE II	613.11	92	1099 CY		CHANNEL
								2900		2900		CY	STONE FILL, TYPE IV	613.13	81	101 CY		ROUNDING
							2			2		EACH	YIELDING MARKER POSTS	619.17	-	1200 CY		TOTAL
							337.5			337.5		LF	STEEL BEAM GUARDRAIL, GALVANIZED	621.20	-	PERMANENT EROSION CONTROL		
							500			500		LF	TEMPORARY TRAFFIC BARRIER	621.90	9	1400 CY		STONE FILL, TYPE II
							450			450		HR	FLAGGERS	630.15	EST.	2900 CY		STONE FILL, TYPE IV
									1	1		LS	FIELD OFFICE, ENGINEERS	631.10	-	750 SY		GEOTEXTILE UNDER STONE FILL
									3000	3000		DL	FIELD OFFICE TELEPHONE (N.A.B.I.)	631.26	-	0.3 TON		HAYMULCH
							1			1		LS	MOBILIZATION/DEMOBILIZATION	635.11	-	1500 SY		TEMPORARY EROSION MATTING
							1			1		LS	TRAFFIC CONTROL	641.10	-	SPECIAL PROVISION (STONE FILL, CHANNEL ARMORING)		
										750		SY	GEOTEXTILE UNDER STONE FILL	649.31	39	8407 CY		TYPE V
										200		SY	GEOTEXTILE FOR SILT FENCE	649.51	42	93 CY		ROUNDING
										50		LB	SEED	651.15	36	8500 CY		TOTAL
										50		LB	SEED, WINTER RYE	651.17	36			
										100		LB	FERTILIZER	651.18	41			
										0.3		TON	AGRICULTURAL LIMESTONE	651.20	0.1			
										0.3		TON	HAY MULCH	651.25	0.1			
							70			70		CY	TOPSOIL	651.35	9			
							1400			1400		SY	GRUBBING MATERIAL	651.40	3			
										1		LS	EPSC PLAN	652.10	-			
										150		HR	MONITORING EPSC PLAN	652.20	-			
										1		LU	MAINTENANCE OF EPSC PLAN (N.A.B.I.)	652.30	-			
										1500		SY	TEMPORARY EROSION MATTING	653.20	16			
										20		CY	TEMPORARY STONE CHECK DAM, TYPE I	653.25	2			
										30		CY	VEHICLE TRACKING PAD	653.35	1			
										1100		LF	BARRIER FENCE	653.50	5			
										1		LU	PRICE ADJUSTMENT, FUEL (N.A.B.I.)	690.50	-			
										8500		CY	SPECIAL PROVISION (STONE FILL, CHANNEL ARMORING)	900.608	93			
										600		LF	SPECIAL PROVISION (TEMPORARY WATER DIVERSION BARRIER)	900.640	87			

PROJECT NAME: WOODFORD
 PROJECT NUMBER: ER NH 010-1(47)
 FILE NAME: z12b402qty.dgn
 PROJECT LEADER: E. ATKINS
 DESIGNED BY: M. BRADLEY
 QUANTITY SHEET

PLOT DATE: 12/03/2014
 DRAWN BY: M. BRADLEY
 CHECKED BY: E. ATKINS
 SHEET 12 OF 35

