

QUANTITY SHEET 1

SUMMARY OF ESTIMATED QUANTITIES										TOTALS		DESCRIPTIONS				DETAILED SUMMARY OF QUANTITIES			
								ROADWAY	EROSION CONTROL	FULL C.E. ITEMS	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	ROUND	QUANTITIES	UNIT	ITEMS
								1			1		LS	CLEARING AND GRUBBING, INCLUDING INDIVIDUAL TREES AND STUMPS	201.10	-			
								3550			3550		CY	COMMON EXCAVATION	203.15	30			
								176			176		CY	SOLID ROCK EXCAVATION	203.16	-			
								650			650		CY	EARTH BORROW	203.30	72			
								100			100		CY	TRENCH EXCAVATION OF EARTH	204.20	13			
								1			1		CY	TRENCH EXCAVATION OF EARTH, EXPLORATORY (N.A.B.I)	204.22	-			
								1350			1350		CY	SUBBASE OF DENSE GRADED CRUSHED STONE	301.35	50			
								50			50		CY	AGGREGATE SHOULDERS, IN PLACE	402.10	14			
								20			20		LF	18" PCCSP .064 (2-2/3 X 1/2)	601.0415	-			
								50			50		LF	18" PCCSP .079 (2-2/3 X 1/2)	601.0416	4			
								60			60		LF	18" CPEP(SL)	601.2615	6			
								2			2		EACH	18" PCCSP ELBOW .064 (2-2/3 X 1/2)	601.5415	-			
								2			2		EACH	18" CPEP ELBOW	601.5814	-			
								1			1		EACH	18" CSPES .064 (2-2/3 X 1/2)	601.6015	-			
								1			1		EACH	18" CPEPES	601.7015	-			
								20			20		CY	STONE FILL, TYPE I	613.10	16.8			
								1400			1400		CY	STONE FILL, TYPE II	613.11	42			
								2600			2600		CY	STONE FILL, TYPE IV	613.13	56			
								2			2		EACH	RELOCATE MAILBOX, SINGLE SUPPORT	617.10	-			
								4			4		EACH	YIELDING MARKER POSTS	619.17	-			
								100			100		LF	STEEL BEAM GUARDRAIL, GALVANIZED	621.20	-			
								2			2		EACH	ENERGY ABSORPTION ATTENUATOR	621.56	-			
								475			475		LF	REMOVE AND RESET GUARDRAIL	621.75	-			
								750			750		LF	TEMPORARY TRAFFIC BARRIER	621.90	19			
								160			160		HR	UNIFORMED TRAFFIC OFFICERS	630.10	-			
								700			700		HR	FLAGGERS	630.15	-			
										1	1		LS	FIELD OFFICE, ENGINEERS	631.10	-			
										3000	3000		DL	FIELD OFFICE TELEPHONE (N.A.B.I)	631.26	-			
								1			1		LS	MOBILIZATION/DEMOBILIZATION	635.11	-			
								1			1		LS	TRAFFIC CONTROL	641.10	-			
								2			2		EACH	PORTABLE CHANGEABLE MESSAGE SIGN	641.15	-			
								2200			2200		LF	DURABLE 4 INCH WHITE LINE, THERMOPLASTIC	646.402	30			
								2200			2200		LF	DURABLE 4 INCH YELLOW LINE, THERMOPLASTIC	646.412	30			
								2200			2200		LF	TEMPORARY 4 INCH WHITE LINE, TEMPORARY PAVEMENT MARKING TAPE	646.6011	30			
								2200			2200		LF	TEMPORARY 4 IN YELLOW LINE, TEMPORARY PAVEMENT MARKING TAPE	646.6111	30			
								1500			1500		SF	PAVEMENT MARKING MASK	646.86	73			
								450			450		SY	GEOTEXTILE UNDER STONE FILL	649.31	41			
								200			200		SY	GEOTEXTILE FOR SILT FENCE, WOVEN WIRE REINFORCED	649.515	11			
								500			500		SY	GEOTEXTILE FOR FILTER CURTAIN	649.61	28			
								50			50		LB	SEED	651.15	5.1			

PROJECT NAME: SEARSBURG
PROJECT NUMBER: NH 010-1(48)

FILE NAME: z12B404qty.dgn
PROJECT LEADER: E. ATKINS
DESIGNED BY: M. BRADLEY
QUANTITY SHEET 1

PLOT DATE: 6/16/2014
DRAWN BY: M. BRADLEY
CHECKED BY: E. ATKINS
SHEET 9 OF 45

