

# QUANTITY SHEET 2

SUMMARY OF ESTIMATED QUANTITIES										TOTALS		DESCRIPTIONS				DETAILED SUMMARY OF QUANTITIES			
								ROADWAY	EROSION CONTROL	FULL C.E. ITEMS	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	ROUND	QUANTITIES	UNIT	ITEMS
									50		50		LB	SEED, WINTER RYE	651.17	5.1			
									200		200		LB	FERTILIZER	651.18	12.9			
									0.8		0.8		TON	AGRICULTURAL LIMESTONE	651.20	0.05			
									0.8		0.8		TON	HAY MULCH	651.25	0.05			
									90		90		CY	TOPSOIL	651.35	4.8			
								1130			1130		SY	GRUBBING MATERIAL	651.40	7.9			
									1		1		LS	EPSC PLAN	652.10	-			
									150		150		HR	MONITORING EPSC PLAN	652.20	EST			
									1		1		LU	MAINTENANCE OF EPSC PLAN (N.A.B.I.)	652.30	-			
									800		800		SY	TEMPORARY EROSION MATTING	653.20	26			
									300		300		SY	PERMANENT EROSION MATTING	653.21	24			
									40		40		CY	VEHICLE TRACKING PAD	653.35	3			
									700		700		LF	BARRIER FENCE	653.50	48			
									650		650		LF	PROJECT DEMARCATION FENCE	653.55	22			
								24			24		LF	SQUARE TUBE SIGN POST AND ANCHOR	675.341	-			
								1			1		EACH	REMOVING SIGNS	675.50	-			
								1			1		EACH	ERECTING SALVAGED SIGNS	675.60	-			
								1			1		LU	PRICE ADJUSTMENT, FUEL (N.A.B.I.)	690.50	-			

PROJECT NAME: SEARSBURG  
PROJECT NUMBER: NH 010-1(48)

FILE NAME: z12B404qty.dgn  
PROJECT LEADER: E. ATKINS  
DESIGNED BY: M. BRADLEY  
QUANTITY SHEET 2

PLOT DATE: 6/16/2014  
DRAWN BY: M. BRADLEY  
CHECKED BY: E. ATKINS  
SHEET 10 OF 45