

QUANTITY SHEET 2

SUMMARY OF ESTIMATED QUANTITIES								TOTALS		DESCRIPTIONS				DETAILED SUMMARY OF QUANTITIES				
						ROADWAY	EROSION CONTROL	BRIDGE (STA. 12+32.46)	FULL C.E. ITEMS	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	ROUND	QUANTITIES	UNIT	ITEMS
							100			100		LB	FERTILIZER	651.18	12			TEMPORARY EROSION CONTROL
							0.4			0.4		TON	AGRICULTURAL LIMESTONE	651.20	0.05			250 SY GEOTEXTILE FOR SILT FENCE
							0.4			0.4		TON	HAY MULCH	651.25	0.05			50 LB SEED, WINTER RYE
							95			95		CY	TOPSOIL	651.35	1			0.4 TON HAY MULCH
							700			700		SY	GRUBBING MATERIAL	651.40	37			1100 SY TEMPORARY EROSION MATTING
							1			1		LS	EPSC PLAN	652.10	-			SPECIAL PROVISION (BITUMINOUS CONCRETE PAVEMENT, SMALL QUANTITY)
							40			40		HR	MONITORING EPSC PLAN	652.20	EST.			171 TON TYPE IIS - INTERMEDIATE COURSE
							1			1		LU	MAINTENANCE OF EPSC PLAN (N.A.B.I.)	652.30	-			146 TON TYPE IIS - BASE COURSE
							1100			1100		SY	TEMPORARY EROSION MATTING	653.20	8			114 TON TYPE IVS - WEARING COURSE
							8			8		CY	TEMPORARY STONE CHECK DAM, TYPE I	653.25	0.4			19 TON ROUNDING
							50			50		CY	VEHICLE TRACKING PAD	653.35	2			450 TON TOTAL
							1250			1250		LF	PROJECT DEMARCATION FENCE	653.55	44			
						17				17		LF	SQUARE TUBE SIGN POST AND ANCHOR	675.341	-			
						2				2		EACH	REMOVING SIGNS	675.50	-			
						2				2		EACH	ERECTING SALVAGED SIGNS	675.60	-			
						12				12		EACH	DELINEATOR WITH STEEL POST	676.10	-			
							1000			1000		CY	SPECIAL PROVISION (STONE FILL, CHANNEL ARMORING)	900.608	-			
							50			50		CY	SPECIAL PROVISION (STONE FILL, CULVERT LINING)	900.608	-			
						1				1		LS	SPECIAL PROVISION (CPM SCHEDULE)	900.645	-			
							1			1		LS	SPECIAL PROVISION (TEMPORARY RELOCATION OF STREAM)	900.645	-			
						1				1		LS	SPECIAL PROVISION (TRAFFIC CONTROL, ALL-INCLUSIVE)	900.645	-			
						1				1		LU	SPECIAL PROVISION (INCENTIVE/DISINCENTIVE)(N.A.B.I.)	900.650	-			
						1				1		LU	SPECIAL PROVISION (MAT DENSITY PAY ADJUSTMENT, SMALL QUANTITY) (N.A.B.I.)	900.650	-			
						1				1		LU	SPECIAL PROVISION (MIXTURE PAY ADJUSTMENT) (N.A.B.I.)	900.650	-			
						450				450		TON	SPECIAL PROVISION (BITUMINOUS CONCRETE PAVEMENT, SMALL QUANTITY)	900.680	19			

PROJECT NAME: JAMAICA
 PROJECT NUMBER: ER STP 013-2(12)
 FILE NAME: z12b474qty.dgn
 PROJECT LEADER: E. ATKINS
 DESIGNED BY: M. BRADLEY
 QUANTITY SHEET 2
 PLOT DATE: 02/27/2015
 DRAWN BY: M. BRADLEY
 CHECKED BY: E. ATKINS
 SHEET 13 OF 48

