

# QUANTITY SHEET 2

SUMMARY OF ESTIMATED QUANTITIES										TOTALS		DESCRIPTIONS				DETAILED SUMMARY OF QUANTITIES			
								ROADWAY	EROSION CONTROL	FULL C.E. ITEMS	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	ROUND	QUANTITIES	UNIT	ITEMS
								4250			4250		LF	REMOVAL AND DISPOSAL OF GUARDRAIL	621.80	29			GEOTEXTILE FOR ROADBED SEPARATOR
								190			190		HR	UNIFORMED TRAFFIC OFFICERS	630.10	EST	2647	SY	EARTHWORKS
								4000			4000		HR	FLAGGERS	630.15	EST	2999	SY	UNSUITABLE SUBBASE MATERIAL (EST.)
										1	1		LS	FIELD OFFICE, ENGINEERS	631.10	--	825	SY	OVER EXCAVATION (EST.)
										1	1		LS	TESTING EQUIPMENT, CONCRETE	631.16	--	9	SY	ROUNDING
										1	1		LS	TESTING EQUIPMENT, BITUMINOUS	631.17	--	6480	SY	TOTAL
										3000	3000		DL	FIELD OFFICE TELEPHONE (N.A.B.I.)	631.26	--			
								1			1		LS	MOBILIZATION/DEMobilIZATION	635.11	--			
								1			1		LS	TRAFFIC CONTROL	641.10	--			
								2			2		EACH	PORTABLE CHANGEABLE MESSAGE SIGN	641.15	--			
														BEGIN OPTION AA					
								13800			13800		LF	DURABLE 4 INCH WHITE LINE, THERMOPLASTIC	646.402	200			
								13800			13800		LF	DURABLE 4 INCH WHITE LINE, POLYUREA	646.404	200			
														END OPTION AA					
														BEGIN OPTION BB					
								13800			13800		LF	DURABLE 4 INCH YELLOW LINE, THERMOPLASTIC	646.412	200			
								13800			13800		LF	DURABLE 4 INCH YELLOW LINE, POLYUREA	646.414	200			
														END OPTION BB					
								27500			27500		LF	TEMPORARY 4 INCH WHITE LINE, PAINT	646.602	300			
								27500			27500		LF	TEMPORARY 4 INCH YELLOW LINE, PAINT	646.612	300			
								2770			2770		EACH	LINE STRIPING TARGETS	646.76	10			
								6480			6480		SY	GEOTEXTILE FOR ROADBED SEPARATOR	649.11	9			
								140			140		SY	GEOTEXTILE UNDER STONE FILL	649.31	4			
									70		70		SY	GEOTEXTILE FOR SILT FENCE, WOVEN WIRE REINFORCED	649.515	EST			
									50		50		LB	SEED	651.15	8			
									360		360		LB	FERTILIZER	651.18	10			
									2		2		TON	AGRICULTURAL LIMESTONE	651.20	0.6			
									0.3		0.3		TON	HAY MULCH	651.25	0.1			
								110			110		CY	TOPSOIL	651.35	5			
									1050		1050		SY	GRUBBING MATERIAL	651.40				
									1		1		LS	EPSC PLAN	652.10	--			
									10		10		HR	MONITORING EPSC PLAN	652.20	--			
									1		1		LU	MAINTENANCE OF EPSC PLAN (N.A.B.I.)	652.30	--			
									3200		3200		SY	TEMPORARY EROSION MATTING	653.20	23			
									60		60		CY	VEHICLE TRACKING PAD	653.35	6			
									15		15		EACH	INLET PROTECTION DEVICE, TYPE I	653.40	--			
									720		720		LF	BARRIER FENCE	653.50	12			
								92			92		SF	TRAFFIC SIGNS, TYPE A	675.20	1.7			
								480			480		LF	SQUARE TUBE SIGN POST AND ANCHOR	675.341	--			
								27			27		EACH	REMOVING SIGNS	675.50	--			

PROJECT NAME: GRANVILLE  
PROJECT NUMBER: ER STP 013-4 (40)

FILE NAME: z12b520.dgn  
PROJECT LEADER: J. TUCKER  
DESIGNED BY: B. BRESLEND  
QUANTITY SHEET 2

PLOT DATE: 7/8/2015  
DRAWN BY: B. BRESLEND  
CHECKED BY: B. MARTIN  
SHEET 15 OF 141