STATE OF VERMONT
AGENCY OF TRANSPORTATION

ITEM DETAIL SHEET 1

BEGIN STATION	END STATION	POS.	204.22 TRENCH EXC. OF EARTH, EXP. (N.A.B.I.)	402.10 AGGREG. SHLDRS. IN PLACE	613.10 STONE FILL, TYPE I	613.11 STONE FILL, TYPE II	613.13 STONE FILL, TYPE IV	613.15 RIPRAP, HEAVY TYPE	621.20 STEEL BEAM G.R. GALV.	621.205 STEEL BEAM G.R. GALV. W/ 8FT POSTS	621.21 HD STEEL BEAM G.R. GALV.	621.50 MANUF. TERMINAL SECTION, FLARED	621.80 REMOVE & DISPOSE G.R.	649.11 GEOTECH. FOR ROADBED SEP.	649.31 GEOTECH. UNDER STONE FILL	651.35 TOPSOIL	651.40 GRUBBING MATERIAL (12")	653.20 TEMP. EROSION MATTING	REMARKS
			CY	CY	CY	CY	CY	CY	LF	LF	LF	EA	LF	SY	SY	CY	SY	SY	
3+00	71+00	LT&RT	1	299			300							2647					ESTIMATED QUANTITIES TO BE USED AS DIRECTED BY THE ENGINEER
3+72.75	4+35.25	RT									25	1	63						
4+00.25	4+62.75	LT									25	1	63						
4+60.25	5+22.75	RT									25	1	62						
4+90	5+65	LT							12.5		25	1	75						
5+50	8+50	LT														105		950	EARTH BERM
8+19.25	15+06.75	LT							625		25	1	159						
8+71	9+80	LT				44	267										182	182	PLACING STONE ON RIVER EMBANKMENT FOR STABILIZATION
9+73	9+84	RT			2										5				INLET/OUTLET PROTECTION FOR NEW CULVERTS
9+80	14+97	LT				269		617									136	136	PLACING STONE ON RIVER EMBANKMENT FOR STABILIZATION
13+48	13+62	RT			3										6			14	INLET/OUTLET PROTECTION FOR NEW CULVERTS
13+69.5	15+32	RT							100		25	1	115						
15+29	15+91.5	LT									25	1	51						
15+34	15+72	RT					56												
15+55	36+30	RT							2025		50		896						
15+63	36+29	RT				1056		2599									550	550	PLACING STONE ON RIVER EMBANKMENT FOR STABILIZATION
19+09	19+20	LT			4										12				INLET/OUTLET PROTECTION FOR NEW CULVERTS
19+73	19+85	LT			4										13				INLET/OUTLET PROTECTION FOR NEW CULVERTS
23+59	23+71	LT			2										5			1	INLET/OUTLET PROTECTION FOR NEW CULVERTS
SUBTOTAL			1	299	15	1369	623	3216	2762.5	-	225	7	1484	2647	41	105	868	1833	

PROJECT NAME: GRANVILLE
PROJECT NUMBER: ER STP 013-4(40)

FILE NAME: z12b520.dgn
PROJECT LEADER: J. TUCKER
DESIGNED BY: B. BRESLEND
ITEM DETAIL SHEET 1

PLOT DATE: 7/8/2015
DRAWN BY: B. BRESLEND
CHECKED BY: A. SANZ
SHEET 16 OF 141