STATE OF VERMONT
AGENCY OF TRANSPORTATION

ITEM DETAIL SHEET 2

BEGIN STATION	END STATION	POS.	204.22 TRENCH EXC. OF EARTH, EXP. (N.A.B.I.)	402.10 AGGREG. SHLDRS. IN PLACE	613.10 STONE FILL, TYPE I	613.11 STONE FILL, TYPE II	613.13 STONE FILL, TYPE IV	613.15 RIPRAP, HEAVY TYPE	621.20 STEEL BEAM G.R. GALV.	621.205 STEEL BEAM G.R. GALV. W/ 8FT POSTS	621.21 HD STEEL BEAM G.R. GALV.	621.50 MANUF. TERMINAL SECTION, FLARED	621.80 REMOVE & DISPOSE G.R.	649.11 GEOTECH. FOR ROADBED SEP.	649.31 GEOTECH. UNDER STONE FILL	651.35 TOPSOIL	651.40 GRUBBING MATERIAL (12")	653.20 TEMP. EROSION MATTING	REMARKS
			CY	CY	CY	CY	CY	CY	LF	LF	LF	EA	LF	SY	SY	CY	SY	SY	
25+62	25+74	LT			2										5			3	INLET/OUTLET PROTECTION FOR NEW CULVERTS
29+18	29+29	LT			2										5			2	INLET/OUTLET PROTECTION FOR NEW CULVERTS
33+09	33+21	LT			4										13				INLET/OUTLET PROTECTION FOR NEW CULVERTS
35+87	36+49.5	LT									25	1	52						
36+56.5	37+56.5	RT							37.5		25	1	101						
36+74.75	42+99.75	LT							562.5		25	1	262						
36+88	42+86	LT				277		781									179	179	PLACING STONE ON RIVER EMBANKMENT FOR STABILIZATION
38+13	38+26	RT			2										6			2	INLET/OUTLET PROTECTION FOR NEW CULVERTS
39+94	40+05	RT			4										12				INLET/OUTLET PROTECTION FOR NEW CULVERTS
41+02	41+14	RT			4										13				INLET/OUTLET PROTECTION FOR NEW CULVERTS
42+26	42+38	RT			4										14				INLET/OUTLET PROTECTION FOR NEW CULVERTS
45+75	47+35.25	LT							100		25	1	160					79	
44+59	44+70	RT			4										12				INLET/OUTLET PROTECTION FOR NEW CULVERTS
46+92.5	47+55	RT									25	1	26						
47+61.5	48+24	LT									25	1	63						
47+81.75	71+00	RT							1443.75	850	25		2073					1070	
52+59	52+71	LT			2										5			5	INLET/OUTLET PROTECTION FOR NEW CULVERTS
56+34	56+47	LT			2										5			2	INLET/OUTLET PROTECTION FOR NEW CULVERTS
66+65	66+77	LT			2										5			2	INLET/OUTLET PROTECTION FOR NEW CULVERTS
SUBTOTAL SHEET 16			1	299	15	1369	623	3216	2762.5	-	225	7	1484	2647	41	105	868	1833	
SUBTOTAL SHEET 17			-	-	32	277	-	781	2143.75	850	175	6	2737	-	95	-	179	1344	
ROUNDING			-	1	3	54	7	53	43.75	25	25	-	29	-	4	5	3	23	
TOTAL			1	300	50	1700	630	4050	4950	875	425	13	4250	2647	140	110	1050	3200	

PROJECT NAME: GRANVILLE
PROJECT NUMBER: ER STP 013-4(40)

FILE NAME: z12b520.dgn
PROJECT LEADER: J. TUCKER
DESIGNED BY: B. BRESLEND
ITEM DETAIL SHEET 2

PLOT DATE: 7/8/2015
DRAWN BY: B. BRESLEND
CHECKED BY: A. SANZ
SHEET 17 OF 141