

EARTHWORKS

																				SUMMARY AND BALANCES																																																	
TOTAL EXCAVATION EARTH AND ROCK		ROCK EXCAVATION		EMBANKMENT						TOTAL EXCAVATION EARTH AND ROCK		ROCK EXCAVATION		EMBANKMENT						TOTAL EXCAVATION EARTH AND ROCK		ROCK EXCAVATION		EMBANKMENT						STATION TO STATION		TOT EXC. EARTH & ROCK C.Y.	ROCK EXCAV C.Y.	EMBANK C.Y.	EXCESSES		ACUMULATIVE EXCESSES																																
STATION	DIST	AREA	VOLUME	AREA	VOLUME	AREA	VOLUME	AREA	VOLUME	STATION	DIST	AREA	VOLUME	AREA	VOLUME	AREA	VOLUME	AREA	VOLUME	STATION	DIST	AREA	VOLUME	AREA	VOLUME	AREA	VOLUME	AREA	VOLUME	STATION TO STATION	TOT EXC. EARTH & ROCK C.Y.	ROCK EXCAV C.Y.	EMBANK C.Y.	CUT	FILL	CUT	FILL																																
	FT.	S.F.	C.Y.	S.F.	C.Y.	S.F.	C.Y.	S.F.	C.Y.		FT.	S.F.	C.Y.	S.F.	C.Y.	S.F.	C.Y.	S.F.	C.Y.		FT.	S.F.	C.Y.	S.F.	C.Y.	S.F.	C.Y.	S.F.	C.Y.																																								
69+50	50	5.9	16			0.0	0																																																														
70+00	50	5.1	10			0.0	0																																																														
70+50	50	7.5	12			0.0	0																																																														
71+00	50	0.0	7			0.0	0																																																														
TO BE USED AS DIRECTED BY ENGINEER					50																																																																
UNSUITABLE SUBBASE MATERIAL			1999																																																																		
OVER EXCAVATION			3300																																																																		
																												REMARKS																																									
<table border="0" style="width: 100%;"> <tr> <td>EARTH AND ROCK EXCAVATION</td> <td style="text-align: right;">17861</td> </tr> <tr> <td>SOLID ROCK EXCAVATION</td> <td style="text-align: right;">50</td> </tr> <tr> <td>EARTH EXCAVATION</td> <td style="text-align: right;">17811</td> </tr> <tr> <td>PLANIMETERED FILL</td> <td style="text-align: right;">145</td> </tr> <tr> <td>LESS FACTORED SOLID ROCK</td> <td style="text-align: right;">0</td> </tr> <tr> <td>LESS DISPLACEMENT OF ANY LARGE STRUCTURES</td> <td style="text-align: right;">0</td> </tr> <tr> <td>NET PLANIMETERED FILL</td> <td style="text-align: right;">145</td> </tr> <tr> <td>OVER EXCAVATION</td> <td style="text-align: right;">3300</td> </tr> <tr> <td>FACTOR</td> <td style="text-align: right;">1.15</td> </tr> <tr> <td>PLANIMETERED FILL INCLUDING FACTOR</td> <td style="text-align: right;">3962</td> </tr> <tr> <td colspan="2">MATERIALS AVAILABLE FOR FILLS</td> </tr> <tr> <td>COMMON EXCAVATION (8000 CY * 1.00)</td> <td style="text-align: right;">8000</td> </tr> <tr> <td>UNCLASSIFIED CHANNEL EXCAVATION (10100 CY * 0.25)</td> <td style="text-align: right;">2525</td> </tr> <tr> <td>UNDERDRAIN EXCAVATION</td> <td style="text-align: right;">0</td> </tr> <tr> <td>STRUCTURE EXCAVATION</td> <td style="text-align: right;">0</td> </tr> <tr> <td>SOLID ROCK EXCAVATION (50 CY * 0.495)</td> <td style="text-align: right;">25</td> </tr> <tr> <td>TOTAL MATERIAL AVAILABLE FOR FILL</td> <td style="text-align: right;">10550</td> </tr> <tr> <td>TOTAL FILL INCLUDING FACTOR</td> <td style="text-align: right;">3962</td> </tr> <tr> <td>TOTAL MATERIAL FOR FILL</td> <td style="text-align: right;">10550</td> </tr> <tr> <td>BORROW</td> <td style="text-align: right;">0</td> </tr> <tr> <td>EXCESS EXCAVATION</td> <td style="text-align: right;">6588</td> </tr> </table>																												EARTH AND ROCK EXCAVATION	17861	SOLID ROCK EXCAVATION	50	EARTH EXCAVATION	17811	PLANIMETERED FILL	145	LESS FACTORED SOLID ROCK	0	LESS DISPLACEMENT OF ANY LARGE STRUCTURES	0	NET PLANIMETERED FILL	145	OVER EXCAVATION	3300	FACTOR	1.15	PLANIMETERED FILL INCLUDING FACTOR	3962	MATERIALS AVAILABLE FOR FILLS		COMMON EXCAVATION (8000 CY * 1.00)	8000	UNCLASSIFIED CHANNEL EXCAVATION (10100 CY * 0.25)	2525	UNDERDRAIN EXCAVATION	0	STRUCTURE EXCAVATION	0	SOLID ROCK EXCAVATION (50 CY * 0.495)	25	TOTAL MATERIAL AVAILABLE FOR FILL	10550	TOTAL FILL INCLUDING FACTOR	3962	TOTAL MATERIAL FOR FILL	10550	BORROW	0	EXCESS EXCAVATION	6588
EARTH AND ROCK EXCAVATION	17861																																																																				
SOLID ROCK EXCAVATION	50																																																																				
EARTH EXCAVATION	17811																																																																				
PLANIMETERED FILL	145																																																																				
LESS FACTORED SOLID ROCK	0																																																																				
LESS DISPLACEMENT OF ANY LARGE STRUCTURES	0																																																																				
NET PLANIMETERED FILL	145																																																																				
OVER EXCAVATION	3300																																																																				
FACTOR	1.15																																																																				
PLANIMETERED FILL INCLUDING FACTOR	3962																																																																				
MATERIALS AVAILABLE FOR FILLS																																																																					
COMMON EXCAVATION (8000 CY * 1.00)	8000																																																																				
UNCLASSIFIED CHANNEL EXCAVATION (10100 CY * 0.25)	2525																																																																				
UNDERDRAIN EXCAVATION	0																																																																				
STRUCTURE EXCAVATION	0																																																																				
SOLID ROCK EXCAVATION (50 CY * 0.495)	25																																																																				
TOTAL MATERIAL AVAILABLE FOR FILL	10550																																																																				
TOTAL FILL INCLUDING FACTOR	3962																																																																				
TOTAL MATERIAL FOR FILL	10550																																																																				
BORROW	0																																																																				
EXCESS EXCAVATION	6588																																																																				
<table border="0" style="width: 100%;"> <tr> <td>PROJECT NAME:</td> <td>GRANVILLE</td> <td>PLOT DATE:</td> <td>7/8/2015</td> </tr> <tr> <td>PROJECT NUMBER:</td> <td>ER STP 013-4(40)</td> <td>DRAWN BY:</td> <td>B. MARTIN</td> </tr> <tr> <td>FILE NAME:</td> <td>z12b520.dgn</td> <td>DESIGNED BY:</td> <td>A. SANZ</td> </tr> <tr> <td>PROJECT LEADER:</td> <td>J. TUCKER</td> <td>CHECKED BY:</td> <td>A. SANZ</td> </tr> <tr> <td>DESIGNED BY:</td> <td>B. MACK</td> <td>EARTHWORKS SHEET 2</td> <td>SHEET 21 OF 141</td> </tr> </table>																												PROJECT NAME:	GRANVILLE	PLOT DATE:	7/8/2015	PROJECT NUMBER:	ER STP 013-4(40)	DRAWN BY:	B. MARTIN	FILE NAME:	z12b520.dgn	DESIGNED BY:	A. SANZ	PROJECT LEADER:	J. TUCKER	CHECKED BY:	A. SANZ	DESIGNED BY:	B. MACK	EARTHWORKS SHEET 2	SHEET 21 OF 141																						
PROJECT NAME:	GRANVILLE	PLOT DATE:	7/8/2015																																																																		
PROJECT NUMBER:	ER STP 013-4(40)	DRAWN BY:	B. MARTIN																																																																		
FILE NAME:	z12b520.dgn	DESIGNED BY:	A. SANZ																																																																		
PROJECT LEADER:	J. TUCKER	CHECKED BY:	A. SANZ																																																																		
DESIGNED BY:	B. MACK	EARTHWORKS SHEET 2	SHEET 21 OF 141																																																																		