

# QUANTITY SHEET 1

SUMMARY OF ESTIMATED QUANTITIES										TOTALS		DESCRIPTIONS				DETAILED SUMMARY OF QUANTITIES		
									ROADWAY	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	ROUND	QUANTITIES	UNIT	ITEMS
									26	26		EACH	THINNING AND TRIMMING FOR SIGNS	201.31	EST			
									1	1		CY	TRENCH EXCAVATION OF EARTH, EXPLORATORY (N.A.B.I.)	204.22	EST			
									80	80		HR	UNIFORMED TRAFFIC OFFICERS	630.10	EST			
									240	240		HR	FLAGGERS	630.15	EST			
									1	1		LS	MOBILIZATION/DEMOBILIZATION	635.11	-			
									1	1		LS	TRAFFIC CONTROL	641.10	-			
									5323	5323		SF	TRAFFIC SIGNS, TYPE A	675.20	-			
									8010	8010		LF	SQUARE TUBE SIGN POST AND ANCHOR	675.341	-			
									886	886		EACH	REMOVING SIGNS	675.50	EST			
									13	13		EACH	ERECTING SALVAGED SIGNS	675.60	EST			
									196	196		EACH	DELINEATOR WITH STEEL POST	676.10	-			
									18	18		EACH	SPECIAL PROVISION (SOIL BEARING SLIP BASE)(2 1/2")	900.620	-			

PROJECT NAME: ALBURGH-COLCHESTER  
PROJECT NUMBER: STPG SIGN(45)



FILE NAME: z12b530qty.dgn  
PROJECT LEADER: D. BRYANT  
DESIGNED BY: B. TOOTHAKER  
QUANTITY SHEET

PLOT DATE: 4/28/2014  
DRAWN BY: J. BLANCHARD  
CHECKED BY: K. KERN  
SHEET 3 OF 167