DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB / FT) 1.88	SQUARE STEEL (IN) 2.00 (LB / FT) 2.42	SQUARE STEEL (IN) 2.50 (LB / FT) 3.35	TUBULAR STEEL Ø (IN) FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB / FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL LOCATION SHSM	SIGN DETAIL LOCATION PROJECT SHEET #	SIGN DETAIL LOCATION STANDARD SHEET #
ALBURGH US-2 EB							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																			"SHSM"-STANDARD HIGHWAY SIGNS AND MARKINGS			
		A	M1-4	24	24								1					15.25											
		A	M3-2	24	12	BLK/ WHT	EAST 11/8/14	2.00								1		X										X	
		A	M1-4	24	24	BLK/ WHT	2	4.00																				X	
EB	1.164	A	VR-048F	24	30		ARRET OBLIGATOIRE SUR FEU ROUGE D'AUTOBUS D'ECOLIERS						1	X																
		A	VR-048	24	30		STATE LAW STOP FOR SCHOOL BUS FLASHING RED LIGHTS						1																
EB	1.297	A	VR-023B	24	30								1	X				13.75											
		A	VR-023B	24	30		$500 MAX FINE THROWING TRASH ON HIGHWAYS AND STREAMS 11/8/14	5.00								1												10	
EB	1.400	A	VR-128B	48	36								1	~~X~~															
		A	VR-601	36	36		SAFETY BELTS 17 REQUIRED 11/8/14	9.00																				10	
EB	1.746	A	W13-1	18	18		45 MPH 11/8/14						1		X														
		A	W1-2ML	30	30		MODIFIED LEFT CURVE						1																
EB	1.782	A	W1-10cL	36	36		11/8/14	9.00								2		16.75 X 16.75									INSTALL 100 FT WEST OF BEGINNING OF CURVE (190 FT EAST OF EXISTING)	X		
EB	1.834	A	W1-8L	18	24		11/8/14	3.00								1		14.75 X									INSTALL 90 FT WEST OF LEFT LARGE ARROW	X		
		B	W1-8R	18	24			3.00																				X	
EB	1.851	A	W1-6	48	24		<=== LEFT LARGE ARROW						1		X														
SIGN SUMMARY SHEET							SHEET TOTALS	35.00	0.00	0	0	0	8	0	0	4		77.25 ~~60.0~~		0	0.0	0.0	0.0	0.0					
								SF	SF	EA	EA	EA	EA	EA	EA	EA		FT		EA	LB	LB	LB	LB					
VERMONT AGENCY OF TRANSPORTATION							TOWN DIRECTIONAL TOTALS	897.8	0.0	37	1	1	165	0	0	92		1380.0		0		0.0							

PROJECT NAME: ALBURGH-COLCHESTER
PROJECT NUMBER: STPG SIGN(45)
FILE NAME: 1 Alburgh US2 EB TSS.xls
PROJECT MANAGER: D. BRYANT
DESIGNED BY: B. TOOTHAKER
ALBURGH EB SHEET 2
PLOT DATE: 4/15/2014
DRAWN BY: J. BLANCHARD
CHECKED K. KERN
SHEET 16 OF 167