DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB/FT) 1.88	SQUARE STEEL (IN) 2.00 (LB/FT) 2.42	SQUARE STEEL (IN) 2.50 (LB/FT) 3.35	TUBULAR STEEL Ø (IN) FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB/FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB/FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB/FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB/FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL LOCATION SHSM	SIGN DETAIL LOCATION PROJECT SHEET #	SIGN DETAIL LOCATION STANDARD SHEET #
ALBURGH US-2 EB							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																				"SHSM"-STANDARD HIGHWAY SIGNS AND MARKINGS			
		C	VD1-1	72	12			6.00																					7	
		C	M3-2	24	12	BLK/WHT		2.00																				X		
		C	M1-4	24	24	BLK/WHT		4.00																				X		
		C	M6-1L	21	15	BLK/WHT		2.19																				X		
		C	M3-4	24	12	BLK/WHT		2.00																				X		
		C	M1-4	24	24	BLK/WHT	12/15/14	4.00																				X		
		C	M6-1R	21	15	BLK/WHT		2.19										14.00 15.50									SLIP BASES	X		
EB	3.195	A	W3-5	48	48								1		X			13.00 13.75												
		A	W3-5	36	36			9.00								2	X											X		
EB	3.265	A	VD-018	30	18								1		X			13.00												
		A	VD-018	30	18		11/10/14	3.75								1	X												6	
EB	3.319	A	R2-1	36	48								1		X			14.75												
		A	R2-1	30	36		11/10/14	7.50								1	X											X		
EB	3.394	A	VR-142	24	36		NO PARKING DEC. 1 - APR. 1 MIDNIGHT TO 7AM			1				X																
		A	M4-6P	24	12		BEGIN PARKING			1																				
							SHEET TOTALS	42.63	0.00	2	0	0	3	0	0	4		~~60.0~~ 84.00		0	0.0	0.0	0.0	0.0					
								SF	SF	EA	EA	EA	EA	EA	EA	EA		FT		EA	LB	LB	LB	LB					
							TOWN DIRECTIONAL TOTALS	897.8	0.0	37	1	1	165	0	0	92		1380.0		0		0.0							

SIGN SUMMARY SHEET

VERMONT AGENCY OF TRANSPORTATION

PROJECT NAME: ALBURGH-COLCHESTER
PROJECT NUMBER: STPG SIGN(45)

FILE NAME: 1 Alburgh US2 EB TSS.xls
PROJECT MANAGER: D. BRYANT
DESIGNED BY: B. TOOTHAKER
ALBURGH EB SHEET 8

PLOT DATE: 4/15/2014
DRAWN BY: J. BLANCHARD
CHECKED K. KERN
SHEET 22 OF 167