DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB/FT) 1.88	SQUARE STEEL (IN) 2.00 (LB/FT) 2.42	SQUARE STEEL (IN) 2.50 (LB/FT) 3.35	TUBULAR STEEL Ø (IN) FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB/FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB/FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB/FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB/FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL LOCATION SHSM	SIGN DETAIL LOCATION PROJECT SHEET #	SIGN DETAIL LOCATION STANDARD SHEET #
ALBURGH US-2 EB							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																				"SHSM"-STANDARD HIGHWAY SIGNS AND MARKINGS			
EB	3.556	A	W3-5	36	36								1	X															
		A	W3-5	36	36		11/10/14	9.00																			X		
EB	3.651	A	R2-1	24	30								1		X														
		A	R2-1	30	36		11/10/14	7.50								1		13.75 X									X		
EB	3.696	A	W16-9	24	10		AHEAD						1		X														
		A	S1-1	30	30								1																
		A	S1-1	36	36	FYG	11/14/14	9.00								1			14.00 X								X		
		A	S4-3	24	8	FYG		1.33																			X		
EB	3.719	A	R2-1	24	30		SPEED LIMIT 25						1	X															
		A	S4-3	24	8		SCHOOL						1																
		A	S4-4	24	10		WHEN FLASHING 11/14/14						1																
		A	S5-1	24	48			8.00																		RETAIN FLASHING BEACON	X		
EB	3.752	A	VR-142	24	36		11/14/14						1	X															
		A	VR-142A	24	18			3.00																				10	
EB	3.892	A	S1-1	30	30		11/14/14						1		X														

SIGN SUMMARY SHEET

VERMONT AGENCY OF TRANSPORTATION

	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN)	TUBULAR STEEL Ø (IN) FOUNDATION	TUBULAR STEEL Ø (IN) 3.00	TUBULAR STEEL Ø (IN) 3.50	TUBULAR STEEL Ø (IN) 4.00	TUBULAR STEEL Ø (IN) 5.00
SHEET TOTALS	37.83	0.00	0	0	0	9	0	0	2	~~27.75~~ 30.0	0	0.0	0.0	0.0	0.0
	SF	SF	EA	EA	EA	EA	EA	EA	EA	FT	EA	LB	LB	LB	LB
TOWN DIRECTIONAL TOTALS	897.8	0.0	37	1	1	165	0	0	92	1380.0	0	0.0			

PROJECT NAME: ALBURGH-COLCHESTER
PROJECT NUMBER: STPG SIGN(45)
FILE NAME: 1 Alburgh US2 EB TSS.xls
PROJECT MANAGER: D. BRYANT
DESIGNED BY: B. TOOTHAKER
ALBURGH EB SHEET 9
PLOT DATE: 4/15/2014
DRAWN BY: J. BLANCHARD
CHECKED K. KERN
SHEET 23 OF 167