DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND		NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB / FT) 1.88	SQUARE STEEL (IN) 2.00 (LB / FT) 2.42	SQUARE STEEL (IN) 2.50 (LB / FT) 3.35	TUBULAR STEEL Ø (IN) FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB / FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL LOCATION SHSM	SIGN DETAIL LOCATION PROJECT SHEET #	SIGN DETAIL LOCATION STANDARD SHEET #
ALBURGH US-2 EB							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																				"SHSM"-STANDARD HIGHWAY SIGNS AND MARKINGS			
		D	R1-1	30	30		STOP	11/11/14	6.25										14.00								HAYLDE RD (TH-27)	X		
EB	5.668	A/B	D3-1	UNK.	UNK..		HAYLDE RD	11/11/14						1		X														
EB	5.861	A	W3-5	36	36									1		X			17.75 16.75											
		A	W3-5	36	36		WEST 40	11/11/14	9.00								2		X									X		
EB	5.930	A	M3-2	24	12		ROUTE MARKER ASSEMBLY							1		X														
		A	M1-4	24	24			11/11/14						1					16.00											
		A	M3-2	24	12	BLK/ WHT	EAST		2.00								1		X									X		
		A	M1-4	24	24	BLK/ WHT	2		4.00																			X		
EB	5.961	C	VR-017	24	30									1	X															
		C	R2-1	24	30		SPEED LIMIT 25	11/11/14			1								17.25								HAYLDE RD (TH-27)			
		C	VR-017	24	30		LEGAL LOAD LIMIT 24,000 POUNDS		5.00																		REQUIRES VEGETATION CLEARING		10	
EB	5.971	D	R1-1	30	30									1	~~X~~															
		A/B	D3-1	UNK.	UNK..									1																
		A/B	D3-1	42	12		Haylde Rd	11/11/14	3.50										16.25								MOUNT TO STOP SIGN WITH BRACKET		12	
		D	R1-1	30	30		STOP		6.25																		HAYLDE RD (TH-27)	X		
SIGN SUMMARY SHEET							SHEET TOTALS		36.00	0.00	1	0	0	7	0	0	3		~~98.00~~ ~~45.0~~		0	0.0	0.0	0.0	0.0					
									SF	SF	EA	EA	EA	EA	EA	EA	EA		FT		EA	LB	LB	LB	LB					
VERMONT AGENCY OF TRANSPORTATION							TOWN DIRECTIONAL TOTALS		897.8	0.0	37	1	1	165	0	0	92		1380.0		0			0.0					

PROJECT NAME: ALBURGH-COLCHESTER
PROJECT NUMBER: STPG SIGN(45)
FILE NAME: 1 Alburgh US2 EB TSS.xls
PROJECT MANAGER: D. BRYANT
DESIGNED BY: B. TOOTHAKER
ALBURGH EB SHEET 16
PLOT DATE: 4/15/2014
DRAWN BY: J. BLANCHARD
CHECKED K. KERN
SHEET 30 OF 167