| DIRECTION | MILEPOINT | LOCATION CODE (SHEET 2) | SIGN CODE | WIDTH (IN) | HEIGHT (IN) | SHEETING REMARKS | SIGN LEGEND | NEW SIGNS "A" | NEW SIGNS "B" | EXISTING SIGNS RETAIN | EXISTING SIGNS SALVAGE FROM | EXISTING SIGNS SALVAGE TO | EXISTING SIGNS REMOVE | EXIST POST RETAIN | EXIST POST REMOVE | NUMBER OF NEW POSTS | SQUARE STEEL (IN) 1.75 (LB/FT) 1.88 | SQUARE STEEL (IN) 2.00 (LB/FT) 2.42 | SQUARE STEEL (IN) 2.50 (LB/FT) 3.35 | TUBULAR STEEL Ø (IN) FOUNDATION | TUBULAR STEEL Ø (IN) 3.00 (LB/FT) 7.60 | TUBULAR STEEL Ø (IN) 3.50 (LB/FT) 9.00 | TUBULAR STEEL Ø (IN) 4.00 (LB/FT) 10.80 | TUBULAR STEEL Ø (IN) 5.00 (LB/FT) 14.60 | SIGN FRAME REQUIRED | REMARKS | SIGN DETAIL LOCATION SHSM | SIGN DETAIL LOCATION PROJECT SHEET # | SIGN DETAIL LOCATION STANDARD SHEET # |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| **ALBURGH US-2 EB** | | | | | | | FY-FLUORESCENT YELLOW<br>FYG-FLUORESCENT YELLOW GREEN | | | | | | | | | | | | | | | | | | | "SHSM"-STANDARD HIGHWAY SIGNS AND MARKINGS | | | |
| EB | 5.987 | A | R4-1 | 24 | 30 | | | | | | | | 1 | | X | | | | | | | | | | | | | | |
| | | A | R2-1 | 24 | 30 | | | | | | | | 1 | | | | | 17.50 | | | | | | | | | | | |
| | | A | R2-1 | 30 | 36 | | SPEED LIMIT 40 12/15/14 | 7.50 | | | | | | | | 1 | | | X | | | | | | | | | X | | |
| | | A | R4-1 | 24 | 30 | | DO NOT PASS | 5.00 | | | | | | | | | | | | | | | | | | | SLIP BASES | X | | |
| EB | 6.016 | A | W2-1 | 30 | 30 | | | 6.25 | | | | | | | | 1 | | 16.25<br>X | | | | | | | | | INSTALL 26 FT WEST OF EXISTING JCT ASSEMBLY | X | | |
| | | A | W16-2P | 24 | 18 | | 1000 FEET 11/11/14 | 3.00 | | | | | | | | | | | | | | | | | | | | X | | |
| EB | 6.021 | A | M2-1 | 21 | 15 | | JCT STATE 11/11/14 | | | | | | 1 | | X | | | | | | | | | | | | | | | |
| | | A | M1-5 | 24 | 24 | | VERMONT 78 | | | | | | 1 | | | | | | | | | | | | | | | | | |
| EB | 6.058 | A | W16-2 | 24 | 12 | | 800 FEET 11/11/14 | | | | | | 1 | | X | | | | | | | | | | | | | | | |
| | | A | W2-1 | 36 | 36 | | CROSSROAD | | | | | | 1 | | | | | 17.00 | | | | | | | | | | | |
| | | A | M2-1 | 21 | 15 | GRN/WHT | JCT | 2.19 | | | | | | | | 1 | | X | | | | | | | | | | X | | |
| | | A | M1-5 | 24 | 24 | GRN/WHT | VERMONT 78 | 4.00 | | | | | | | | | | | | | | | | | | | | X | | |
| EB | 6.093 | A | VD-062AS | 72 | 16 | | BUSINESS SIGN | | | 1 | | | | X | | | | | | | | | | | | | | | | |
| | | A | VD-062AS | 72 | 16 | | BUSINESS SIGN | | | 1 | | | | X | | | | | | | | | | | | | | | | |
| EB | 6.130 | A | D1-1 | 72 | 10 | | D-BOARD ASSEMBLY 04/15/15 | | | | | | 1 | | X | | | | | | | | | | | | | | | |
| | | | | | | | SHEET TOTALS | 27.94 | 0.00 | 2 | 0 | 0 | 7 | 0 | 0 | 3 | | 50.75<br>~~45.0~~ | | 0 | 0.0 | 0.0 | 0.0 | 0.0 | | | | | |
| | | | | | | | | SF | SF | EA | EA | EA | EA | EA | EA | EA | | FT | | EA | LB | LB | LB | LB | | | | | |
| | | | | | | | TOWN DIRECTIONAL TOTALS | 897.8 | 0.0 | 37 | 1 | 1 | 165 | 0 | 0 | 92 | | 1380.0 | | 0 | | 0.0 | | | | | | | |

# SIGN SUMMARY SHEET

VERMONT AGENCY OF TRANSPORTATION

PROJECT NAME: ALBURGH-COLCHESTER
PROJECT NUMBER: STPG SIGN(45)
FILE NAME: 1 Alburgh US2 EB TSS.xls
PROJECT MANAGER: D. BRYANT
DESIGNED BY: B. TOOTHAKER
ALBURGH EB SHEET 17
PLOT DATE: 4/15/2014
DRAWN BY: J. BLANCHARD
CHECKED K. KERN
SHEET 31 OF 167