DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB / FT) 1.88	SQUARE STEEL (IN) 2.00 (LB / FT) 2.42	SQUARE STEEL (IN) 2.50 (LB / FT) 3.35	FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB / FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL LOCATION SHSM	SIGN DETAIL LOCATION PROJECT SHEET #	SIGN DETAIL LOCATION STANDARD SHEET #
ALBURGH US-2 EB							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																			"SHSM"-STANDARD HIGHWAY SIGNS AND MARKINGS			
		A	M1-1	24	24	WHT/ BLU		4.00																			X		
		A	M6-1L	21	15	WHT/ BLU		2.19																			X		
		A	M3-2	24	12	GRN/ WHT		2.00																			X		
		A	M1-5	24	24	GRN/ WHT		4.00																			X		
		A	M6-1L	21	15	GRN/ WHT		2.19																			X		
		A	M3-2	24	12	BLK/ WHT		2.00																			X		
		A	M1-4	24	24	BLK/ WHT		4.00																			X		
		A	M6-3	21	15	BLK/ WHT		2.19																			X		
EB	6.232	D	R1-1	30	30								1	~~X~~												TRUCK ROUTE (TH-4)			
		D	R1-1	30	30		11/11/14	6.25										14.50								INSTALL WEST OF INTERSECTION; TRUCK ROUTE (TH-4)	X		
		C	VR-017	24	30			5.00																		INSTALL ON REVERSE OF STOP SIGN; TRUCK ROUTE (TH-4)		10	
EB	6.236	D	R1-1	30	30		11/11/14						1	X															
		A/B	D3-1	UNK.	UNK..		TRUCK ROUTE (STREET SIGN)						1																
		D	R1-1	30	30			6.25																		TRUCK ROUTE (TH-4)	X		
EB	6.236	A/B	D3-1	54	12		Truck Route	4.50								2		11.00 X 11.00								TRUCK ROUTE (TH-4); FIELD LOCATE FOR VISIBILITY FROM ROUTE 2		12	
SIGN SUMMARY SHEET							SHEET TOTALS	44.56	0.00	0	0	0	3	0	0	2		36.50 ~~30.0~~			0	0.0	0.0	0.0	0.0				
								SF	SF	EA	EA	EA	EA	EA	EA	EA		FT			EA	LB	LB	LB	LB				
VERMONT AGENCY OF TRANSPORTATION							TOWN DIRECTIONAL TOTALS	897.8	0.0	37	1	1	165	0	0	92		1380.0			0		0.0						

PROJECT NAME: ALBURGH-COLCHESTER
PROJECT NUMBER: STPG SIGN(45)
FILE NAME: 1 Alburgh US2 EB TSS.xls
PROJECT MANAGER: D. BRYANT
DESIGNED BY: B. TOOTHAKER
ALBURGH EB SHEET 19
PLOT DATE: 4/15/2014
DRAWN BY: J. BLANCHARD
CHECKED K. KERN
SHEET 33 OF 167