DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB / FT) 1.88	SQUARE STEEL (IN) 2.00 (LB / FT) 2.42	SQUARE STEEL (IN) 2.50 (LB / FT) 3.35	TUBULAR STEEL Ø (IN) FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB / FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL LOCATION SHSM	SIGN DETAIL LOCATION PROJECT SHEET #	SIGN DETAIL LOCATION STANDARD SHEET #
ALBURGH US-2 EB							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																			"SHSM"-STANDARD HIGHWAY SIGNS AND MARKINGS			
EB	7.772	D	R1-1	30	30		11/24/14						1	~~X~~															
		A/B	D3-1	UNK.	UNK..								1					14.00											
		A/B	D3-1	40	12		Middle Rd	3.33																		MIDDLE RD (TH-33); MOUNT ON STOP SIGN WITH BRACKET		12	
		D	R1-1	30	30		STOP	6.25																		MIDDLE RD (TH-33)	X		
EB	7.906	A	W1-2R	30	30		RIGHT CURVE 11/24/14						1		X														
EB	7.970	A	W1-2R	30	30		11/24/14	6.25					1			1		15.75 X								INSTALL 100 FT WEST OF BEGINNING OF CURVE (338 FT EAST OF EXISTING)	X		
EB	8.291 - 8.400	A/B	N/A	6	8		INSTALL (10) NEW DELINEATOR ASSEMBLIES 11/24/14																			INSTALL 10 BACK TO BACK DELINEATOR ASSEMBLIES AT 60 FT SPACINGS. SEE SHEET 4			
EB	9.657	A	W11-1	30	30								1		X			15.75											
		A	W11-1	30	30		11/24/14	6.25								1		X									X		
EB	9.661	A	W11-3A	30	30								1		X				15.50										
		A	W11-3	30	30		11/24/14	6.25								1			X								X		
		A	W16-4P	30	24		NEXT 1½ MILES	5.00																			X		
EB	9.736	A	S3-1T	30	30		SCHOOL BUS STOP AHEAD 11/24/14						1		X														
EB	9.752	A	W1-2L	30	30		11/24/14	6.25								1		14.00 X								INSTALL 100 FT WEST OF BEGINNING OF CURVE (84 FT EAST OF EXISTING SBSA)	X		
EB	9.802	C	VR-017	24	30		11/24/14						1	X															
							SHEET TOTALS	39.58	0.00	0	0	0	8	0	0	4		75.00 ~~60.0~~		0	0.0	0.0	0.0	0.0					
								SF	SF	EA	EA	EA	EA	EA	EA	EA		FT		EA	LB	LB	LB	LB					
							TOWN DIRECTIONAL TOTALS	897.8	0.0	37	1	1	165	0	0	92		1380.0		0		0.0							

SIGN SUMMARY SHEET

VERMONT AGENCY OF TRANSPORTATION

PROJECT NAME: ALBURGH-COLCHESTER
PROJECT NUMBER: STPG SIGN(45)

FILE NAME: 1 Alburgh US2 EB TSS.xls
PROJECT MANAGER: D. BRYANT
DESIGNED BY: B. TOOTHAKER
ALBURGH EB SHEET 22

PLOT DATE: 4/15/2014
DRAWN BY: J. BLANCHARD
CHECKED K. KERN
SHEET 36 OF 167