DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB/FT) 1.88	SQUARE STEEL (IN) 2.00 (LB/FT) 2.42	SQUARE STEEL (IN) 2.50 (LB/FT) 3.35	TUBULAR STEEL Ø (IN) FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB/FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB/FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB/FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB/FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL LOCATION SHSM	SIGN DETAIL LOCATION PROJECT SHEET #	SIGN DETAIL LOCATION STANDARD SHEET #
ALBURGH US-2 EB							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																				"SHSM"-STANDARD HIGHWAY SIGNS AND MARKINGS			
		A	M6-1	21	15								1																
		A	M3-2	24	12	BLK/WHT		2.00								2		12.50 X 12.50								#2	SLIP BASES	X		
		A	M1-4	24	24	BLK/WHT		4.00																				X		
		A	M6-3	21	15	BLK/WHT		2.19																				X		
		A	M3-4	24	12	GRN/WHT		2.00																			X		
		A	M1-5	30	24	GRN/WHT		5.00																				X		
		A	M6-1R	21	15	GRN/WHT		2.19																				X		
EB	11.632	A	M1-5	30	24		ROUTE 129 11/25/14						1		X														
EB	11.660	A	M3-2	24	12		ROUTE MARKER ASSEMBLY						1		X														
		A	M1-4	24	24		11/25/14						1					16.50											
		A	M3-2	24	12	BLK/WHT		2.00								1		X										X		
		A	M1-4	24	24	BLK/WHT		4.00																				X		
EB	11.672	A	W2-2MR	30	30								1		X			15.75											
		A	W2-2R	30	30		11/25/14	6.25								1		X										X		
EB	11.719	A	D3-1	56	12		04/17/15	4.67								2		11.25 X 11.50									POOR FARM RD (TH-38); INSTALL AT CORNER OF RED HOUSE FOR VISIBILITY FROM ROUTE 2		12	
							SHEET TOTALS	34.30	0.00	0	0	0	5	0	0	6		~~80.00~~ ~~90.0~~		0	0.0	0.0	0.0	0.0				
								SF	SF	EA	EA	EA	EA	EA	EA	EA		FT		EA	LB	LB	LB	LB				
							TOWN DIRECTIONAL TOTALS	897.8	0.0	37	1	1	165	0	0	92		1380.0		0		0.0						

SIGN SUMMARY SHEET

VERMONT AGENCY OF TRANSPORTATION

PROJECT NAME: **ALBURGH-COLCHESTER**
PROJECT NUMBER: **STPG SIGN(45)**

FILE NAME: **1 Alburgh US2 EB TSS.xls**
PROJECT MANAGER: **D. BRYANT**
DESIGNED BY: **B. TOOTHAKER**
ALBURGH EB SHEET 26

PLOT DATE: **4/15/2014**
DRAWN BY: **J. BLANCHARD**
CHECKED **K. KERN**
SHEET **40** OF **167**