DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB/FT) 1.88	SQUARE STEEL (IN) 2.00 (LB/FT) 2.42	SQUARE STEEL (IN) 2.50 (LB/FT) 3.35	TUBULAR STEEL Ø (IN) FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB/FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB/FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB/FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB/FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL LOCATION SHSM	SIGN DETAIL LOCATION PROJECT SHEET #	SIGN DETAIL LOCATION STANDARD SHEET #
ALBURGH US-2 WB							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																			"SHSM"-STANDARD HIGHWAY SIGNS AND MARKINGS			
		F	M1-4	24	24								1			2		14.25 14.25											
		F	M4-5	24	12								1																
		F	M1-5A	24	24								1																
		F	M3-4	24	12	BLK/ WHT	04/15/15	2.00																	#1		X		
		F	M1-4	24	24	BLK/ WHT		4.00																			X		
		F	M4-5	24	12	BLK/ WHT	WEST TO 2 11	2.00																			X		
		F	M1-4	24	24	BLK/ WHT		4.00																			X		
WB	5.997	F	R2-1	24	30								1	~~X~~				12.75											
		F	VR-417	30	30		END NO PASSING						1																
		E	W14-3	48	36								1																
		F	R2-1	24	30		SPEED LIMIT 50 11/13/14	5.00																			X		
		F	R4-2	24	30		PASS WITH CARE	5.00																			MOUNT BELOW SPEED LIMIT	X		
		E	W14-3	48	36		NO PASSING ZONE	12.00																			MOUNT ON REVERSE OF SPEED LIMIT	X		
WB	5.824 - 5.625	F/G	N/A	6	8		INSTALL (15) NEW DELINEATOR ASSEMBLIES																				INSTALL 15 BACK TO BACK DELINEATOR ASSEMBLIES AT 75 FT SPACINGS. SEE SHEET 4			
WB	5.796	F	W1-2L	30	30		11/13/14						1	X															
							SHEET TOTALS	34.00	0.00	0	0	0	7	0	0	0		41.25 0.0			0	0.0	0.0	0.0	0.0					
								SF	SF	EA	EA	EA	EA	EA	EA	EA		FT			EA	LB	LB	LB	LB					
							TOWN DIRECTIONAL TOTALS	870.8	0.0	23	3	2	157	0	0	80		1200.0			0	0.0								

SIGN SUMMARY SHEET

VERMONT AGENCY OF TRANSPORTATION

PROJECT NAME: **ALBURGH-COLCHESTER**
PROJECT NUMBER: **STPG SIGN(45)**

FILE NAME: **2 Alburgh US2 WB TSS.xls** PLOT DATE: **4/15/2014**
PROJECT MANAGER: **D. BRYANT** DRAWN BY: **J. BLANCHARD**
DESIGNED BY: **B. TOOTHAKER** CHECKED **K. KERN**
ALBURGH WB SHEET 9 SHEET **50** OF **167**