DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB/FT) 1.88	SQUARE STEEL (IN) 2.00 (LB/FT) 2.42	SQUARE STEEL (IN) 2.50 (LB/FT) 3.35	TUBULAR STEEL Ø (IN) FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB/FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB/FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB/FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB/FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL LOCATION SHSM	SIGN DETAIL LOCATION PROJECT SHEET #	SIGN DETAIL LOCATION STANDARD SHEET #
ALBURGH US-2 WB							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																			"SHSM"-STANDARD HIGHWAY SIGNS AND MARKINGS			
		F	W13-1	18	18		45 MPH						1																
		F	W1-2L	30	30			6.25																			X		
WB	5.422	F	W3-5	48	48		11/13/14						1		X														
		F	W3-5	36	36			9.00								2		15.00 X 15.50								X		
WB	5.368	F	VD-018	30	18		11/13/14	3.75								1		15.00 X								INSTALL 250 FT EAST OF SPEED LIMIT SIGN		6	
WB	5.321	F	R2-1	36	48		11/13/14						1		X			15.75											
		F	R2-1	30	36			7.50								1		X									X		
WB	5.198	F	R2-1	24	30		SPEED LIMIT 40 11/13/14						1		X														
WB	5.180	F	VD-018	30	18		ALBURGH ROUSES POINT 4 11/13/14						1		X														
WB	5.048	F	R2-1	24	30								1		X			15.50											
		F	R2-1	24	30		11/13/14	5.00								1		X									X		
WB	4.931	F	W1-10R	30	30								1	X				15.00											
		F	W13-1	18	18		40 MPH 11/13/14						1																
		F	W1-10R	36	36			9.00																		RETAIN EXISTING FLASHING BEACON	X		
WB	4.878	F	M4-6P	24	12		BEGIN PARKING			1				X															
SIGN SUMMARY SHEET							SHEET TOTALS	40.50	0.00	1	0	0	8	0	0	5		91.75 ~~75.0~~		0	0.0	0.0	0.0	0.0					
								SF	SF	EA	EA	EA	EA	EA	EA	EA		FT		EA	LB	LB	LB	LB					
VERMONT AGENCY OF TRANSPORTATION							TOWN DIRECTIONAL TOTALS	870.8	0.0	23	3	2	157	0	0	80		1200.0		0		0.0							

PROJECT NAME: **ALBURGH-COLCHESTER**
PROJECT NUMBER: **STPG SIGN(45)**
FILE NAME: **2 Alburgh US2 WB TSS.xls** PLOT DATE: **4/15/2014**
PROJECT MANAGER: **D. BRYANT** DRAWN BY: **J. BLANCHARD**
DESIGNED BY: **B. TOOTHAKER** CHECKED **K. KERN**
ALBURGH WB SHEET 10 SHEET **51** OF **167**