| DIRECTION | MILEPOINT | LOCATION CODE (SHEET 2) | SIGN CODE | WIDTH (IN) | HEIGHT (IN) | SHEETING REMARKS | SIGN LEGEND | NEW SIGNS "A" | NEW SIGNS "B" | EXISTING SIGNS RETAIN | EXISTING SIGNS SALVAGE FROM | EXISTING SIGNS SALVAGE TO | EXISTING SIGNS REMOVE | EXIST POST RETAIN | EXIST POST REMOVE | NUMBER OF NEW POSTS | SQUARE STEEL (IN) 1.75 (LB/FT) 1.88 | SQUARE STEEL (IN) 2.00 (LB/FT) 2.42 | SQUARE STEEL (IN) 2.50 (LB/FT) 3.35 | TUBULAR STEEL Ø (IN) FOUNDATION | TUBULAR STEEL Ø (IN) 3.00 (LB/FT) 7.60 | TUBULAR STEEL Ø (IN) 3.50 (LB/FT) 9.00 | TUBULAR STEEL Ø (IN) 4.00 (LB/FT) 10.80 | TUBULAR STEEL Ø (IN) 5.00 (LB/FT) 14.60 | SIGN FRAME REQUIRED | REMARKS | SIGN DETAIL LOCATION SHSM | SIGN DETAIL LOCATION PROJECT SHEET # | SIGN DETAIL LOCATION STANDARD SHEET # |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| **ALBURGH US-2 WB** | | | | | | | FY-FLUORESCENT YELLOW<br>FYG-FLUORESCENT YELLOW GREEN | | | | | | | | | | | | | | | | | | | | "SHSM"-STANDARD HIGHWAY SIGNS AND MARKINGS | | | |
| WB | 4.493 | F | R2-1 | 24 | 30 | | | | | | | | 1 | | X | | | 15.00 | | | | | | | | | | | |
| | | F | R2-1 | 24 | 30 | | 11/14/14 | 5.00 | | | | | | | | 1 | | X | | | | | | | | | REQUIRES VEGETATION CLEARING | X | | |
| WB | 4.468 | F | VR-142 | 24 | 36 | | NO PARKING DEC. 1 - APR. 1 MIDNIGHT TO 7AM | | | 1 | | | | X | | | | | | | | | | | | | | | |
| WB | 4.437 | G | VR-017 | 24 | 30 | | | | | | | | 1 | X | | | | | | | | | | | | | | | |
| | | G | R2-1 | 24 | 30 | | SPEED LIMIT 25 | | | 1 | | | | | | | | | | | | | | | | | JARVIS LN (TH-53) | | | |
| | | G | VR-017 | 24 | 30 | | 11/13/14 | 5.00 | | | | | | | | | | | | | | | | | | | JARVIS LN (TH-53) | | 10 | |
| WB | 4.430 | H | R1-1 | 30 | 30 | | | | | | | | 1 | X | | | | | | | | | | | | | | | |
| | | F | D3-1 | UNK. | UNK. | | | | | | | | 1 | | | | | | | | | | | | | | | | |
| | | F | D3-1 | 40 | 12 | | 11/13/14 | 3.33 | | | | | | | | | | | | | | | | | | | JARVIS LN (TH-53); MOUNT TO STOP SIGN WITH BRACKET | | 12 | |
| | | H | R1-1 | 30 | 30 | | | 6.25 | | | | | | | | | | | | | | | | | | | JARVIS LN (TH-53) | X | | |
| WB | 4.429 | F | R2-1 | 24 | 30 | | SPEED LIMIT 30 11/13/14 | 5.00 | | 1 | | | | X | | | | 15.00 | | | | | | | | | | | |
| WB | 4.372 | F | R2-1 | 24 | 30 | | SPEED LIMIT 30 11/14/14 | | | | | | 1 | | X | | | | | | | | | | | | | | |
| WB | 4.274 | F | VR-660 | 24 | 30 | | NO PARKING ON SIDEWALK OR TRAVEL LANE | | | 1 | | | | X | | | | | | | | | | | | | | | |
| WB | 4.240 | F | VR-142 | 24 | 36 | | NO PARKING DEC. 1 - APR. 1 MIDNIGHT TO 7AM | | | 1 | | | | X | | | | | | | | | | | | | | | |
| | | F | R2-1 | 24 | 30 | | SPEED LIMIT 30 | | | 1 | | | | | | | | | | | | | | | | | | | |
| **SIGN SUMMARY SHEET** | | | | | | | SHEET TOTALS | ~~24.58~~ 19.58 SF | 0.00 SF | 6 EA | 0 EA | 0 EA | 5 EA | 0 EA | 0 EA | 1 EA | | ~~30.00~~ 15.0 FT | | 0 EA | 0.0 LB | 0.0 LB | 0.0 LB | 0.0 LB | | | | | |
| VERMONT AGENCY OF TRANSPORTATION | | | | | | | TOWN DIRECTIONAL TOTALS | 870.8 | 0.0 | 23 | 3 | 2 | 157 | 0 | 0 | 80 | | 1200.0 | | 0 | 0.0 | | | | | | | | |

PROJECT NAME: ALBURGH-COLCHESTER
PROJECT NUMBER: STPG SIGN(45)
FILE NAME: 2 Alburgh US2 WB TSS.xls
PROJECT MANAGER: D. BRYANT
DESIGNED BY: B. TOOTHAKER
ALBURGH WB SHEET 13
PLOT DATE: 4/15/2014
DRAWN BY: J. BLANCHARD
CHECKED K. KERN
SHEET 54 OF 167