DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB/FT) 1.88	SQUARE STEEL (IN) 2.00 (LB/FT) 2.42	SQUARE STEEL (IN) 2.50 (LB/FT) 3.35	TUBULAR STEEL Ø (IN) FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB/FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB/FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB/FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB/FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL LOCATION SHSM	SIGN DETAIL LOCATION PROJECT SHEET #	SIGN DETAIL LOCATION STANDARD SHEET #
ALBURGH US-2 WB							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																				"SHSM"-STANDARD HIGHWAY SIGNS AND MARKINGS			
WB	4.218	G	VR-017	24	30								1	X															
		G	R2-1	24	30		SPEED LIMIT 25			1																	VANTINE AVE (TH-25)			
		G	VR-017	24	30		LEGAL LOAD LIMIT 24,000 POUNDS 11/13/14	5.00										16.00									VANTINE AVE (TH-25)		10	
WB	4.212	H	R1-1	30	30								1		X														
		F	D3-1	UNK.	UNK.		VANTINE AVE						1					14.50											
		H	R1-1	30	30		STOP 11/13/14	6.25								1		X									VANTINE AVE (TH-25)	X		
WB	4.212	G	UNK.	UNK.	UNK.		DEAD END						1		X														
WB	4.212	F	D3-1	50	12		Vantine Ave 11/14/14	4.17								2		11.25 X 10.50									VANTINE AVE (TH-25); FIELD LOCATE FOR VISIBILITY FROM ROUTE 2		12	
WB	4.191	F	W11-2	30	30								1		X														
		F	W11-2	30	30	FYG	11/14/14	6.25								1			15.75 X									X		
		F	W16-4P	30	24	FYG	NEXT 500 FT	5.00																				X		
WB	4.140	G	VR-017	24	30		LEGAL LOAD LIMIT 24,000 POUNDS 11/14/14	5.00								1		13.00 X									PETERSON PL (TH-48); INSTALL AT EDGE OF GAS STATION PARKING LOT		10	
WB	4.144	H	R1-1	30	30																								
		H	R1-1	30	30		STOP 11/14/14	6.25								1		13.00 X									PETERSON PL (TH-48)	X		
WB	4.144	F	D3-1	42	12		Peterson Pl 11/14/14	3.50								1		10.75 X									PETERSON PL (TH-48); FIELD LOCATE FOR VISIBILITY FROM ROUTE 2		13	
SIGN SUMMARY SHEET							SHEET TOTALS	41.42	0.00	1	0	0	5	0	0	7		104.75 ~~105.0~~		0	0.0	0.0	0.0	0.0					
								SF	SF	EA	EA	EA	EA	EA	EA	EA		FT		EA	LB	LB	LB	LB					
VERMONT AGENCY OF TRANSPORTATION							TOWN DIRECTIONAL TOTALS	870.8	0.0	23	3	2	157	0	0	80		1200.0		0		0.0							

PROJECT NAME: **ALBURGH-COLCHESTER**
PROJECT NUMBER: **STPG SIGN(45)**

FILE NAME: **2 Alburgh US2 WB TSS.xls** PLOT DATE: **4/15/2014**
PROJECT MANAGER: **D. BRYANT** DRAWN BY: **J. BLANCHARD**
DESIGNED BY: **B. TOOTHAKER** CHECKED **K. KERN**
ALBURGH WB SHEET 14 SHEET **55** OF **167**