DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB/FT) 1.88	SQUARE STEEL (IN) 2.00 (LB/FT) 2.42	SQUARE STEEL (IN) 2.50 (LB/FT) 3.35	TUBULAR STEEL Ø (IN) FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB/FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB/FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB/FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB/FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL LOCATION SHSM	SIGN DETAIL LOCATION PROJECT SHEET #	SIGN DETAIL LOCATION STANDARD SHEET #
ALBURGH US-2 WB							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																				"SHSM"-STANDARD HIGHWAY SIGNS AND MARKINGS			
WB	4.137	F	W11-8	30	30								1		X														
		F	W11-8	30	30		11/14/14	6.25								1		13.75 X									X		
WB	4.092	F	R2-1	24	30		11/14/14	5.00								1		13.00 X								INSTALL 237 FT WEST OF FIRE ENGINE SYMBOL	X		
WB	4.048	F	W16-9	24	10		AHEAD						1	X													SALVAGE SNOWMOBILE SIGN			
		F	S1-1	30	30								1																
		F	UNK.	UNK.	UNK.		VAST TRAIL ACCESS PARKING				1		1														SALVAGE SIGN AND RETURN TO TOWN			
		F	S1-1	36	36	FYG	11/14/14	9.00																			X		
		F	S3-4	12	8	FYG		0.67																			X		
WB	4.043	F	D3-1	UNK.	UNK.		INDUSTRIAL PARK RD 11/14/14						1		X														
WB	4.041	G	R2-1	24	30		SPEED LIMIT 25				1	1	1	X													INDUSTRIAL PARK RD (TH-59); SALVAGE AND REMOUNT BELOW LLL			
		G	VR-017	24	30		11/14/14	5.00																			INDUSTRIAL PARK RD (TH-59)		10	
WB	4.035	H	R1-1	30	30								1	X															
		H	R1-1	30	30		11/14/14	6.25																			INDUSTRIAL PARK RD (TH-59)	X		
WB	4.035	F	D3-1	72	12		11/14/14	6.00								2		11.00 X 10.75									INDUSTRIAL PARK RD (TH-59); FIELD LOCATE FOR VISIBILITY FROM ROUTE 2		13	
WB	4.020	H	R1-1	30	30		11/14/14						1	X															
SIGN SUMMARY SHEET							SHEET TOTALS	38.17	0.00	0	2	1	8	0	0	4		48.50 ~~60.0~~		0	0.0	0.0	0.0	0.0					
								SF	SF	EA	EA	EA	EA	EA	EA	EA		FT		EA	LB	LB	LB	LB					
VERMONT AGENCY OF TRANSPORTATION							TOWN DIRECTIONAL TOTALS	870.8	0.0	23	3	2	157	0	0	80		1200.0		0			0.0					

PROJECT NAME: **ALBURGH-COLCHESTER**
PROJECT NUMBER: **STPG SIGN(45)**
FILE NAME: **2 Alburgh US2 WB TSS.xls** PLOT DATE: **4/15/2014**
PROJECT MANAGER: **D. BRYANT** DRAWN BY: **J. BLANCHARD**
DESIGNED BY: **B. TOOTHAKER** CHECKED **K. KERN**
ALBURGH WB SHEET 15 SHEET **56** OF **167**