DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB/FT) 1.88	SQUARE STEEL (IN) 2.00 (LB/FT) 2.42	SQUARE STEEL (IN) 2.50 (LB/FT) 3.35	TUBULAR STEEL Ø (IN) FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB/FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB/FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB/FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB/FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL LOCATION SHSM	SIGN DETAIL LOCATION PROJECT SHEET #	SIGN DETAIL LOCATION STANDARD SHEET #
ALBURGH US-2 WB							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																			"SHSM"-STANDARD HIGHWAY SIGNS AND MARKINGS			
		F	D3-1	UNK.	UNK.								1																
		F	D3-1	30	12		Milk St	2.50																		MILK ST (TH-57); MOUNT TO STOP SIGN WITH BRACKET		13	
		H	R1-1	30	30		STOP 11/14/14	6.25																		MILK ST (TH-57); INSTALL ON SOUTH SIDE OF INTERSECTION	X		
		G	VR-017	24	30		LEGAL LOAD LIMIT 24,000 POUNDS	5.00																		MILK ST (TH-57); MOUNT ON REVERSE OF STOP SIGN		10	
WB	3.966	F	R2-1	24	30		SPEED LIMIT 25						1	X															
		F	S4-4	24	10		WHEN FLASHING						1																
		F	S4-3	24	10		SCHOOL 11/14/14						1																
		F	S5-1	24	48		SCHOOL SPEED LIMIT 25 WHEN FLASHING	8.00																		RETAIN FLASHING BEACON	X		
WB	3.940	G	VR-660	24	36								1	X															
		G	VR-142	24	36								1																
		G	VR-660	24	30		NO PARKING ON SIDEWALK OR TRAVEL LANE 11/14/14	5.00																		REQUIRES VEGETATION CLEARING		10	
		G	VR-142A	24	36		TOW-AWAY ZONE DEC 1 - APR 1	6.00																				10	
WB	3.920	F	W16-7	24	12								1	X															
		F	S1-1	30	30		11/14/14						1																
		F	S1-1	36	36	FYG		9.00																			X		
SIGN SUMMARY SHEET							SHEET TOTALS	41.75	0.00	0	0	0	8	0	0	0	0.0			0	0.0	0.0	0.0	0.0					
								SF	SF	EA	EA	EA	EA	EA	EA	EA	FT			EA	LB	LB	LB	LB					
VERMONT AGENCY OF TRANSPORTATION							TOWN DIRECTIONAL TOTALS	870.8	0.0	23	3	2	157	0	0	80	1200.0			0	0.0								

PROJECT NAME: ALBURGH-COLCHESTER
PROJECT NUMBER: STPG SIGN(45)
FILE NAME: 2 Alburgh US2 WB TSS.xls
PROJECT MANAGER: D. BRYANT
DESIGNED BY: B. TOOTHAKER
ALBURGH WB SHEET 16
PLOT DATE: 4/15/2014
DRAWN BY: J. BLANCHARD
CHECKED K. KERN
SHEET 57 OF 167