| DIRECTION | MILEPOINT | LOCATION CODE (SHEET 2) | SIGN CODE | WIDTH (IN) | HEIGHT (IN) | SHEETING REMARKS | SIGN LEGEND | NEW SIGNS "A" | NEW SIGNS "B" | EXISTING SIGNS RETAIN | EXISTING SIGNS SALVAGE FROM | EXISTING SIGNS SALVAGE TO | EXISTING SIGNS REMOVE | EXIST POST RETAIN | EXIST POST REMOVE | NUMBER OF NEW POSTS | SQUARE STEEL (IN) 1.75 (LB/FT) 1.88 | SQUARE STEEL (IN) 2.00 (LB/FT) 2.42 | SQUARE STEEL (IN) 2.50 (LB/FT) 3.35 | TUBULAR STEEL Ø (IN) FOUNDATION | TUBULAR STEEL Ø (IN) 3.00 (LB/FT) 7.60 | TUBULAR STEEL Ø (IN) 3.50 (LB/FT) 9.00 | TUBULAR STEEL Ø (IN) 4.00 (LB/FT) 10.80 | TUBULAR STEEL Ø (IN) 5.00 (LB/FT) 14.60 | SIGN FRAME REQUIRED | REMARKS | SIGN DETAIL LOCATION SHSM | SIGN DETAIL LOCATION PROJECT SHEET # | SIGN DETAIL LOCATION STANDARD SHEET # |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| **NORTH HERO US-2 EB** | | | | | | | FY-FLUORESCENT YELLOW<br>FYG-FLUORESCENT YELLOW GREEN | | | | | | | | | | | | | | | | | | | | "SHSM"-STANDARD HIGHWAY SIGNS AND MARKINGS | | | |
| EB | 2.853 | A | D1-1E | 72 | 20 | | 12/02/14 | | | | | | 1 | X | | | | 11.75 | | | | | | | | | | | |
| | | A | VD2-1 | 72 | 20 | | North Hero Elementary School → | 10.00 | | | | | | | | | | | | | | | | | | | | 9 | |
| EB | 2.924 | D | R1-1 | 30 | 30 | | | | | | | | 1 | X | | | | | | | | | | | | | | | |
| | | D | R1-1 | 30 | 30 | | STOP 12/02/14 | 6.25 | | | | | | | | | | | | | | | | | | | LOCATED ON SCHOOL ENTRANCE | X | | |
| EB | 3.090 | A | W2-2MR | 30 | 30 | | RIGHT SIDE ROAD | | | | | | 1 | | X | | | | | | | | | | | | | | |
| EB | 3.221 | A | W2-2 | 30 | 30 | | 12/02/14 | 6.25 | | | | | | | | 1 | | 17.00 X | | | | | | | | | INSTALL 250 FT WEST OF INTERSECTION | X | | |
| EB | 3.228 | A/B | D3-1 | 68 | 12 | | Blockhouse Point Rd 12/02/14 | 5.67 | | | | | | | | 2 | | 12.50 X 13.25 | | | | | | | | | BLOCKHOUSE POINT RD (TH-7); FIELD LOCATE FOR VISIBILITY FROM ROUTE 2 | | 13 | |
| EB | 3.229 | C | VR-017 | 24 | 30 | | | | | | | | 1 | X | | | | 13.50 | | | | | | | | | | | |
| | | C | VR-017 | 24 | 30 | | LEGAL LOAD LIMIT 24,000 POUNDS 12/02/14 | 5.00 | | | | | | | | | | | | | | | | | | | BLOCKHOUSE POINT RD (TH-7) | | 10 | |
| EB | 3.239 | D | R1-1 | 30 | 30 | | | | | | | | 1 | X | | | | 12.00 | | | | | | | | | | | |
| | | D | R1-1 | 30 | 30 | | STOP 12/02/14 | 6.25 | | | | | | | | | | | | | | | | | | | BLOCKHOUSE POINT RD (TH-7) | X | | |
| EB | 3.240 | A/B | D3-1 | UNK | 12 | | BLOCKHOUSE POINT RD | | | | | | 1 | | X | | | | | | | | | | | | | | |
| EB | 3.793 | A | R2-1 | 24 | 30 | | | | | | | | 1 | X | | | | | | | | | | | | | | | |
| | | A | R2-1 | 24 | 30 | | SPEED LIMIT 50 12/02/14 | 5.00 | | | | | | | | | | | | | | | | | | | | X | | |
| EB | 3.862 | A | VW-205 | 36 | 36 | | | | | | | | 1 | X | | | | | | | | | | | | | | | |
| | | | | | | | SHEET TOTALS | 44.42 SF | 0.00 SF | 0 EA | 0 EA | 0 EA | 8 EA | 0 EA | 0 EA | 3 EA | | 80.00 45.0 FT | | | 0 EA | 0.0 LB | 0.0 LB | 0.0 LB | 0.0 LB | | | | | |
| | | | | | | | TOWN DIRECTIONAL TOTALS | 320.7 | 0.0 | 8 | 1 | 0 | 57 | 0 | 0 | 30 | | 450.0 | | | 0 | 0.0 | | | | | | | | | | |

## SIGN SUMMARY SHEET

VERMONT AGENCY OF TRANSPORTATION

PROJECT NAME: ALBURGH-COLCHESTER
PROJECT NUMBER: STPG SIGN(45)
FILE NAME: 3 NORTH HERO US2 EB TSS.xls PLOT DATE: 3/14/2014
PROJECT MANAGER: D. BRYANT DRAWN BY: J. BLANCHARD
DESIGNED BY: B. TOOTHAKER CHECKED K. KERN
NORTH HERO EB SHEET 3 SHEET 69 OF 167