DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB/FT) 1.88	SQUARE STEEL (IN) 2.00 (LB/FT) 2.42	SQUARE STEEL (IN) 2.50 (LB/FT) 3.35	TUBULAR STEEL Ø (IN) FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB/FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB/FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB/FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB/FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL LOCATION SHSM	SIGN DETAIL LOCATION PROJECT SHEET #	SIGN DETAIL LOCATION STANDARD SHEET #
NORTH HERO US-2 WB							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																				"SHSM"-STANDARD HIGHWAY SIGNS AND MARKINGS			
WB	9.212	E	W3-3	36	36		SIGNAL AHEAD			1				X															
WB	9.165	E	W3-6	36	36		DRAWBRIDGE AHEAD			1				X															
WB	9.060	G	VR-278	24	36		12/05/14						1	X															
		G	VR-278	24	36			6.00										16.00								10	
WB	9.025	F	VW-205	30	30		WATCH FOR TURNING VEHICLES 12/05/14						1		X														
WB	8.971	F	VW-205	36	36		12/05/14	9.00								~~1~~ 2		16.25 X								INSTALL 250 FT EASTT OF SPEED LIMIT 50 SIGN			E-154
WB	8.924	F	R2-1	24	30								1	X															
		F	R2-1	24	30		12/05/14	5.00										16.00									X		
WB	8.319	F	VD-062B	72	16		BUSINESS SIGN			1				X															
WB	8.159	F	M3-4	24	12		ROUTE MARKER ASSEMBLY						1	X					10.50										
		F	M1-4	24	24		12/05/14						1																
		F	M3-4	24	12	BLK/WHT		2.00										16.00									X		
		F	M1-4	24	24	BLK/WHT		4.00																			X		
WB	6.532	F	S3-1T	30	30		SCHOOL BUS STOP AHEAD 12/04/14						1		X														
WB	6.402	F	W3-5	48	48		12/04/14						1		X														
							SHEET TOTALS	26.00	0.00	3	0	0	7	0	0	2		~~74.75~~ ~~30.0~~		0	0.0	0.0	0.0	0.0					
								SF	SF	EA	EA	EA	EA	EA	EA	EA		FT		EA	LB	LB	LB	LB					
							TOWN DIRECTIONAL TOTALS	363.5	0.0	10	1	0	67	0	0	37		555.0		0			0.0						

SIGN SUMMARY SHEET

VERMONT AGENCY OF TRANSPORTATION

PROJECT NAME: ALBURGH-COLCHESTER
PROJECT NUMBER: STPG SIGN(45)
FILE NAME: 4 NORTH HERO US2 WB TSS.xl
PROJECT MANAGER: D. BRYANT
DESIGNED BY: B. TOOTHAKER
NORTH HERO WB SHEET 1
PLOT DATE: 3/14/2014
DRAWN BY: J. BLANCHARD
CHECKED K. KERN
SHEET 76 OF 167