DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB/FT) 1.88	SQUARE STEEL (IN) 2.00 (LB/FT) 2.42	SQUARE STEEL (IN) 2.50 (LB/FT) 3.35	TUBULAR STEEL Ø (IN) FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB/FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB/FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB/FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB/FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL LOCATION SHSM	SIGN DETAIL LOCATION PROJECT SHEET #	SIGN DETAIL LOCATION STANDARD SHEET #
GRAND ISLE US-2 EB							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																				"SHSM"-STANDARD HIGHWAY SIGNS AND MARKINGS			
EB	1.782	C/D	D3-1	42	12		US Route 2 11/21/14	3.50								2		12.25 X 12.00								GRISWOLD RD (TH-1); MOUNT TO STREET NAME SIGN WITH BRACKET		13	
		A/B	D3-1	58	12		Griswold Rd TH1	4.83																		GRISWOLD RD (TH-1); FIELD LOCATE FOR VISIBILITY FROM ROUTE 2		13	
EB	2.465	A	W3-5	48	48		11/21/14						1		X			15.25 15.50											
		A	W3-5	36	36		40	9.00								2		X									X		
EB	2.526	A	VD-018	30	18		Grand Isle Keeler Bay 4 11/21/14	3.75								1		13.75 X								INSTALL 250 FT WEST OF SPEED LIMIT SIGN		6	
EB	2.573	A	R2-1	36	48								1		X			14.75											
		A	R2-1	30	36		SPEED LIMIT 40 11/21/14	7.50								1		X									X		
EB	2.668	A	UNK.	UNK.	UNK.		HISTORIC SITE MARKER AHEAD 11/21/14				1		1		X											SALVAGE AND RETURN TO TOWN			
		A	UNK.	UNK.	UNK.		400TH ANNIVERSARY				1		1													SALVAGE AND RETURN TO TOWN			
EB	2.745	A	W16-9	36	20		AHEAD						1	X															
		A	S1-1	36	36		11/21/14						1																
		A	S1-1	36	36	FYG	SCHOOL	9.00																			X		
		A	S4-3	24	8	FYG		1.33																			X		
EB	2.959	A	S4-3	24	8		SCHOOL 11/24/14						1	X															
		A	R2-1	24	30		SPEED LIMIT 35						1																
SIGN SUMMARY SHEET							SHEET TOTALS	38.91	0.00	0	2	0	8	0	0	6		83.50 ~~96.0~~		0	0.0	0.0	0.0	0.0					
								SF	SF	EA	EA	EA	EA	EA	EA	EA		FT		EA	LB	LB	LB	LB					
VERMONT AGENCY OF TRANSPORTATION							TOWN DIRECTIONAL TOTALS	319.6	0.0	19	2	0	61	0	0	33		495.0		0	0.0								

PROJECT NAME: ALBURGH-COLCHESTER
PROJECT NUMBER: STPG SIGN(45)

FILE NAME: 5 GRAND ISLE US2 EB TSS.xls PLOT DATE: 3/14/2014
PROJECT MANAGER: D. BRYANT DRAWN BY: J. BLANCHARD
DESIGNED BY: B. TOOTHAKER CHECKED K. KERN
GRAND ISLE EB SHEET 3 SHEET 88 OF 167