| DIRECTION | MILEPOINT | LOCATION CODE (SHEET 2) | SIGN CODE | WIDTH (IN) | HEIGHT (IN) | SHEETING REMARKS | SIGN LEGEND | NEW SIGNS "A" | NEW SIGNS "B" | EXISTING SIGNS RETAIN | EXISTING SIGNS SALVAGE FROM | EXISTING SIGNS SALVAGE TO | EXISTING SIGNS REMOVE | EXIST POST RETAIN | EXIST POST REMOVE | NUMBER OF NEW POSTS | SQUARE STEEL (IN) 1.75 (LB / FT) 1.88 | SQUARE STEEL (IN) 2.00 (LB / FT) 2.42 | SQUARE STEEL (IN) 2.50 (LB / FT) 3.35 | TUBULAR STEEL Ø (IN) FOUNDATION | TUBULAR STEEL Ø (IN) 3.00 (LB / FT) 7.60 | TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00 | TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80 | TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60 | SIGN FRAME REQUIRED | REMARKS | SIGN DETAIL LOCATION SHSM | SIGN DETAIL LOCATION PROJECT SHEET # | SIGN DETAIL LOCATION STANDARD SHEET # |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| **GRAND ISLE US-2 EB** | | | | | | | FY-FLUORESCENT YELLOW<br>FYG-FLUORESCENT YELLOW GREEN | | | | | | | | | | | | | | | | | | | "SHSM"-STANDARD HIGHWAY SIGNS AND MARKINGS | | | |
| | | A | S4-4 | 24 | 10 | | WHEN FLASHING | | | | | | 1 | | | | | | | | | | | | | | | | |
| | | A | S5-1 | 24 | 48 | | | 8.00 | | | | | | | | | | | | | | | | | RETAIN EXISTING FLASHING BEACONS | X | | |
| EB | 2.906 | A | VD-018 | 30 | 18 | | GRAND ISLE KEELERS BAY 4 | | | 1 | | | | X | | | | | | | | | | | | | | | |
| EB | 2.952 | A | S5-2 | 24 | 30 | | 11/24/14 | | | | | | 1 | X | | | | | | | | | | | | | | | |
| | | A | S5-2 | 24 | 30 | | | 5.00 | | | | | | | | 1 | | X | | | | | | | | X | |
| EB | 2.986 | A | VD-026BC | 74.75 | 16 | | BUSINESS SIGN | | | 1 | | | | X | | | | | | | | | | | | | | | |
| EB | 3.072 | A | W16-8A | 36 | 20 | | | | | | | | 1 | | X | | | | | | | | | | | | | | |
| | | A | W2-1M | 36 | 36 | | | | | | | | 1 | | | | | 15.25<br>16.00 | | | | | | | | | | | |
| | | A | W2-1 | 30 | 30 | | 11/24/14 | 6.25 | | | | | | | | 2 | | X | | | | | | | | | X | | |
| | | A | W16-8aP | 48 | 15 | | | 5.00 | | | | | | | | | | | | | | | | | | | 7 | |
| EB | 3.054 | A | R2-1 | 30 | 36 | | | | | | | | 1 | X | | | | | | | | | | | | | | | |
| | | A | R2-1 | 30 | 36 | | 11/24/14 | 7.50 | | | | | | | | | | | | | | | | | | | X | | |
| EB | 3.104 | C | VR-017 | 24 | 30 | | 11/24/14 | | | | | | 1 | X | | | | | | | | | | | | | | | |
| | | C | VR-017 | 24 | 30 | | | 5.00 | | | | | | | | 1 | | X | 14.25 | | | | | | | | HYDE RD (TH-2) | | 10 | |
| EB | 3.110 | D | R1-1 | 30 | 30 | | 11/24/14 | | | | | | 1 | X | | | | | | | | | | | | | | | |
| **SIGN SUMMARY SHEET** | | | | | | | SHEET TOTALS | 36.75 | 0.00 | 2 | 0 | 0 | 7 | 0 | 0 | 3 | | 45.50<br>45.0 | | 0 | 0.0 | 0.0 | 0.0 | 0.0 | | | | | |
| | | | | | | | | SF | SF | EA | EA | EA | EA | EA | EA | EA | | FT | | EA | LB | LB | LB | LB | | | | | |
| VERMONT AGENCY OF TRANSPORTATION | | | | | | | TOWN DIRECTIONAL TOTALS | 319.6 | 0.0 | 19 | 2 | 0 | 61 | 0 | 0 | 33 | | 495.0 | | 0 | 0.0 | | | | | | | | |

PROJECT NAME: ALBURGH-COLCHESTER
PROJECT NUMBER: STPG SIGN(45)
FILE NAME: 5 GRAND ISLE US2 EB TSS.xls PLOT DATE: 3/14/2014
PROJECT MANAGER: D. BRYANT DRAWN BY: J. BLANCHARD
DESIGNED BY: B. TOOTHAKER CHECKED K. KERN
GRAND ISLE EB SHEET 4 SHEET 89 OF 167