DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB/FT) 1.88	SQUARE STEEL (IN) 2.00 (LB/FT) 2.42	SQUARE STEEL (IN) 2.50 (LB/FT) 3.35	TUBULAR STEEL Ø (IN) FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB/FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB/FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB/FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB/FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL LOCATION SHSM	SIGN DETAIL LOCATION PROJECT SHEET #	SIGN DETAIL LOCATION STANDARD SHEET #
GRAND ISLE US-2 EB							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																				"SHSM"-STANDARD HIGHWAY SIGNS AND MARKINGS			
		A	D3-1	UNK.	UNK.		HYDE RD TH2						1					13.25											
		A	R1-1	30	30		STOP 12/01/14	6.25										X									HYDE RD (TH-2); REQUIRES VEGETATION CLEARING	X		
EB	3.110	A	D3-1	42	12		US Route 2 11/24/14	3.50								1		11.75 X									HYDE RD (TH-2); MOUNT TO STREET NAME SIGN WITH BRACKET		13	
		D	D3-1	42	12		Hyde Rd TH2	3.50																			HYDE RD (TH-2); FIELD LOCATE FOR VISIBILITY FROM ROUTE 2		13	
EB	3.107	D	R1-1	30	30		11/24/14						1		X														
		D	R1-1	30	30		STOP	6.25								1		13.75 X									HYDE RD (TH-2)	X		
EB	3.138	A	M3-2	24	12		ROUTE MARKER ASSEMBLY						1	X															
		A	M1-4	24	24		11/24/14						1																
		A	M3-2	24	12	BLK/WHT	EAST	2.00																				X		
		A	M1-4	24	24	BLK/WHT	2	4.00																				X		
EB	3.233	B	W2-1	30	30								1	X															
		B	W13-1	18	18		35 MPH 11/24/14						1																
		B	W2-1	30	30			6.25																				X		
EB	3.443	A	R2-1	24	30								1	X															
		A	R2-1	24	30		SPEED LIMIT 40 11/24/14	5.00																				X		
SIGN SUMMARY SHEET							SHEET TOTALS	36.75	0.00	0	0	0	7	0	0	2		38.75 ~~30.0~~		0	0.0	0.0	0.0	0.0					
								SF	SF	EA	EA	EA	EA	EA	EA	EA		FT		EA	LB	LB	LB	LB					
VERMONT AGENCY OF TRANSPORTATION							TOWN DIRECTIONAL TOTALS	319.6	0.0	19	2	0	61	0	0	33		495.0		0		0.0							

PROJECT NAME: ALBURGH-COLCHESTER
PROJECT NUMBER: STPG SIGN(45)
FILE NAME: 5 GRAND ISLE US2 EB TSS.xls
PROJECT MANAGER: D. BRYANT
DESIGNED BY: B. TOOTHAKER
GRAND ISLE EB SHEET 5
PLOT DATE: 3/14/2014
DRAWN BY: J. BLANCHARD
CHECKED K. KERN
SHEET 90 OF 167