DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB/FT) 1.88	SQUARE STEEL (IN) 2.00 (LB/FT) 2.42	SQUARE STEEL (IN) 2.50 (LB/FT) 3.35	TUBULAR STEEL Ø (IN) FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB/FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB/FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB/FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB/FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL LOCATION SHSM	SIGN DETAIL LOCATION PROJECT SHEET #	SIGN DETAIL LOCATION STANDARD SHEET #
GRAND ISLE US-2 WB							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																				"SHSM"-STANDARD HIGHWAY SIGNS AND MARKINGS			
WB	6.248	G	VR-017	24	30								1	X															
		G	VR-017	24	30		11/25/14	5.00																		TOWN LINE RD (TH-3/SOUTH HERO)		10	
WB	6.248	H	R1-1	30	30								1	X															
		H	R1-1	30	30		12/02/14	6.25																		TOWN LINE RD (TH-3/SOUTH HERO)	X		
WB	6.237	H	R1-1	30	30								1	X															
		H	R1-1	30	30		12/02/14	6.25																		TOWN LINE RD (TH-3/SOUTH HERO)	X		
WB	6.236	E/F	D3-1	UNK.	UNK.		11/25/14						1		X														
		E/F	D3-1	42	12			3.50										11.50 11.75								TOWN LINE RD (TH-3/SOUTH HERO); MOUNT TO STREET NAME SIGN WITH BRACKET		13	
		E/F	D3-1	54	12			4.50								2		X								TOWN LINE RD (TH-3/SOUTH HERO); FIELD LOCATE FOR VISIBILITY FROM ROUTE 2		14	
WB	5.780	F	VD-062BRN	72	16		BUSINESS SIGN			1				X															
WB	5.641	F	W2-2R	30	30		11/25/14						1		X			15.00											
		F	W2-2R	30	30			6.25								1		X									X		
WB	5.342	G	VR-017	24	30								1	X															
		G	VR-017	24	30		11/25/14	5.00																		DONALDSON RD (TH-4); REQUIRES VEGETATION CLEARING		10	
WB	5.342	H	R1-1	30	30		STOP						1		X														
SIGN SUMMARY SHEET							SHEET TOTALS	36.75	0.00	1	0	0	7	0	0	3		38.25 ~~45.0~~		0	0.0	0.0	0.0	0.0					
								SF	SF	EA	EA	EA	EA	EA	EA	EA		FT		EA	LB	LB	LB	LB					
VERMONT AGENCY OF TRANSPORTATION							TOWN DIRECTIONAL TOTALS	409.7	0.0	14	0	0	69	0	0	51		765.0		0		0.0							

PROJECT NAME: **ALBURGH-COLCHESTER**
PROJECT NUMBER: **STPG SIGN(45)**
FILE NAME: **6 GRAND ISLE US2 WB TSS.xls** PLOT DATE: **4/28/2014**
PROJECT MANAGER: **D. BRYANT** DRAWN BY: **J. BLANCHARD**
DESIGNED BY: **B. TOOTHAKER** CHECKED **K. KERN**
GRAND ISLE WB SHEET 1 SHEET **96** OF **167**