DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB / FT) 1.88	SQUARE STEEL (IN) 2.00 (LB / FT) 2.42	SQUARE STEEL (IN) 2.50 (LB / FT) 3.35	TUBULAR STEEL Ø (IN) FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB / FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL LOCATION SHSM	SIGN DETAIL LOCATION PROJECT SHEET #	SIGN DETAIL LOCATION STANDARD SHEET #
GRAND ISLE US-2 WB							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																			"SHSM"-STANDARD HIGHWAY SIGNS AND MARKINGS			
WB	0.185	F	VW-170A	48	48		DRAW BRIDGE AHEAD			1				X															
WB	0.125	F	W3-3	30	30		SIGNAL AHEAD SYMBOL			1				X															
WB	0.071	F	VW-666	30	30		BICYCLES USE CAUTION			1				X															
WB	0.050	F	R10-6	24	36		12/02/14						1	X															
		F	R10-6	24	36			6.00																	SALVAGE AND REMOUNT EXISTING ORANGE FLAGS	X		
WB	0.046	G	VR-070P	21	15		<===> DOUBLE ARROW 12/02/14						1	X															
		G	R8-3A	24	24		NO PARKING SYMBOL						1																
		G	VP-136	24	12		ANYTIME						1																
		G	R7-1	24	30			5.00																		X		
	0.047			48	9		TOWN LINE RD	3.00																					
SIGN SUMMARY SHEET							SHEET TOTALS	14.00 ~~11.00~~	0.00	3	0	0	4	0	0	0		0.0		0	0.0	0.0	0.0	0.0					
								SF	SF	EA	EA	EA	EA	EA	EA	EA		FT		EA	LB	LB	LB	LB					
VERMONT AGENCY OF TRANSPORTATION							TOWN DIRECTIONAL TOTALS	412.73 ~~409.7~~	0.0	14	0	0	68 ~~69~~	0	0	51		698.75 ~~765.0~~		0	0.0								

PROJECT NAME: ALBURGH-COLCHESTER
PROJECT NUMBER: STPG SIGN(45)

FILENAME: 6 GRAND ISLE US2 WB TSS.xls
PLOT DATE: 4/28/2014
PROJECT MANAGER: D. BRYANT
DRAWN BY: J. BLANCHARD
DESIGNED BY: B. TOOTHAKER
CHECKED: K. KERN
GRAND ISLE WB SHEET 11
SHEET 106 OF 167