| DIRECTION | MILEPOINT | LOCATION CODE (SHEET 2) | SIGN CODE | WIDTH (IN) | HEIGHT (IN) | SHEETING REMARKS | SIGN LEGEND | NEW SIGNS "A" | NEW SIGNS "B" | EXISTING SIGNS RETAIN | EXISTING SIGNS SALVAGE FROM | EXISTING SIGNS SALVAGE TO | EXISTING SIGNS REMOVE | EXIST POST RETAIN | EXIST POST REMOVE | NUMBER OF NEW POSTS | SQUARE STEEL (IN) 1.75 (LB / FT) 1.88 | SQUARE STEEL (IN) 2.00 (LB / FT) 2.42 | SQUARE STEEL (IN) 2.50 (LB / FT) 3.35 | TUBULAR STEEL Ø (IN) FOUNDATION | TUBULAR STEEL Ø (IN) 3.00 (LB / FT) 7.60 | TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00 | TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80 | TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60 | SIGN FRAME REQUIRED | REMARKS | SIGN DETAIL LOCATION SHSM | SIGN DETAIL LOCATION PROJECT SHEET # | SIGN DETAIL LOCATION STANDARD SHEET # |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| **SOUTH HERO US-2 EB** | | | | | | | FY-FLUORESCENT YELLOW<br>FYG-FLUORESCENT YELLOW GREEN | | | | | | | | | | | | | | | | | | | "SHSM"-STANDARD HIGHWAY SIGNS AND MARKINGS | | | |
| EB | 0.000 | C | VD-024 | 60 | 7.5 | | 11/18/14 | | | | | | 1 | | X | | | 10.25<br>12.50 | | | | | | | | | | | |
| | | C | VD-024 | 72 | 10 | | South Hero \| Grand Isle | 5.00 | | | | | | | | 2 | | X | | | | | | | | | | 7 | |
| | | C | VD-700 | 6 | 10 | | 0020 0705 0000 / 0020 0702 0627 | 0.42 | | | | | | | | | | | | | | | | | | | | | E-138 |
| | | C | VD-700 | 6 | 10 | | | 0.42 | | | | | | | | | | | | | | | | | | | | | E-138 |
| EB | 0.755 | A | W3-5 | 48 | 48 | | | | | | | | 1 | | X | | | 15.25<br>15.75 | | | | | | | | | | | |
| | | A | W3-5 | 36 | 36 | | SPEED LIMIT 40 11/18/14 | 9.00 | | | | | | | | 2 | | X | | | | | | | | | X | | |
| EB | 0.797 | A | W1-2L | 30 | 30 | | | | | | | | 1 | | X | | | 15.25 | | | | | | | | | | | |
| | | A | W1-2L | 30 | 30 | | 11/18/14 | 6.25 | | | | | | | | 1 | | X | | | | | | | | | X | | |
| EB | 0.866 | A | VD-018 | 30 | 18 | | Keeler Bay South Hero 2 11/18/14 | 3.75 | | | | | | | | 1 | | 11.75<br>X | | | | | | | | INSTALL 250 FT WEST OF SPEED LIMIT SIGN | | 6 | |
| EB | 0.913 | A | R2-1 | 36 | 48 | | | | | | | | 1 | ~~X~~ | | | | 15.00 | | | | | | | | | | | |
| | | A | R2-1 | 30 | 36 | | SPEED LIMIT 40 11/18/14 | 7.50 | | | | | | | | | | | | | | | | | | | X | | |
| EB | 0.972 | A | M2-1 | 21 | 15 | | JCT STATE | | | 1 | | | | X | | | | | | | | | | | | | | | |
| | | A | M1-5 | 30 | 24 | | VERMONT 314 | | | 1 | | | | | | | | | | | | | | | | | | | |
| EB | 1.010 | A | VD-062AL | 72 | 16 | | BUSINESS SIGN | | | 1 | | | | X | | | | | | | | | | | | | | | |
| | | A | VD-062B | 72 | 16 | | BUSINESS SIGN | | | 1 | | | | X | | | | | | | | | | | | | | | |
| | | | | | | | SHEET TOTALS | 32.33 | 0.00 | 4 | 0 | 0 | 4 | 0 | 0 | 6 | | 95.75<br>~~98.0~~ | | 0 | 0.0 | 0.0 | 0.0 | 0.0 | | | | | |
| | | | | | | | | SF | SF | EA | EA | EA | EA | EA | EA | EA | | FT | | EA | LB | LB | LB | LB | | | | | |
| | | | | | | | TOWN DIRECTIONAL TOTALS | 257.0 | 0.0 | 48 | 9 | 9 | 57 | 0 | 0 | 29 | | 435.0 | | 0 | | 0.0 | | | | | | | |

## SIGN SUMMARY SHEET

VERMONT AGENCY OF TRANSPORTATION

PROJECT NAME: ALBURGH-COLCHESTER
PROJECT NUMBER: STPG SIGN(45)

FILE NAME: 7 SOUTH HERO US2 EB TSS.xls
PROJECT MANAGER: D. BRYANT
DESIGNED BY: B. TOOTHAKER
SOUTH HERO EB SHEET 1

PLOT DATE: 3/14/2014
DRAWN BY: J. BLANCHARD
CHECKED: K. KERN