DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB/FT) 1.88	SQUARE STEEL (IN) 2.00 (LB/FT) 2.42	SQUARE STEEL (IN) 2.50 (LB/FT) 3.35	TUBULAR STEEL Ø (IN) FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB/FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB/FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB/FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB/FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL LOCATION SHSM	SIGN DETAIL LOCATION PROJECT SHEET #	SIGN DETAIL LOCATION STANDARD SHEET #
SOUTH HERO US-2 EB							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																				"SHSM"-STANDARD HIGHWAY SIGNS AND MARKINGS			
EB	2.633	C	VR-017	24	30								1		X														
		C	VR-017	24	30		11/18/14	5.00								1		13.75 X								TRACY RD (TH-4)		10	
EB	2.634	A/B	D3-1	UNK.	UNK.		TRACY RD 11/18/14						1		X														
EB	2.643	D	R1-1	30	30								1	X															
		A/B	D3-1	36	12		11/18/14	3.00										13.75								TRACY RD (TH-4); MOUNT TO STOP SIGN WITH BRACKET		14	
		D	R1-1	30	30			6.25								1										TRACY RD (TH-4)	X		
EB	2.659	A	R2-1	24	30		SPEED LIMIT 35	5.00		1				X															
EB	2.711	A	VD-062B	72	16		BUSINESS SIGN			1				X															
		A	VD-062B	72	16		BUSINESS SIGN			1																			
		A	VD-062AL	72	16		BUSINESS SIGN			1																			
EB	2.912	A	W11-8	30	30		11/18/14						1		X			13.75											
		A	W11-8	30	30			6.25								1		X									X		
EB	2.934	A	R2-1	24	30		11/18/14						1		X			13.00											
		A	R2-1	24	30			5.00								1		X									X		
EB	2.984	A	W11-2	30	30								1	X															
SIGN SUMMARY SHEET							SHEET TOTALS	~~30.50~~ 25.50 SF	0.00 SF	4 EA	0 EA	0 EA	6 EA	0 EA	0 EA	3 EA		~~54.25~~ 45.0 FT		0 EA	0.0 LB	0.0 LB	0.0 LB	0.0 LB					
VERMONT AGENCY OF TRANSPORTATION							TOWN DIRECTIONAL TOTALS	257.0	0.0	48	9	9	57	0	0	29		435.0		0	0.0								

PROJECT NAME: ALBURGH-COLCHESTER
PROJECT NUMBER: STPG SIGN(45)
FILE NAME: 7 SOUTH HERO US2 EB TSS.xls
PROJECT MANAGER: D. BRYANT
DESIGNED BY: B. TOOTHAKER
SOUTH HERO EB SHEET 5
PLOT DATE: 3/14/2014
DRAWN BY: J. BLANCHARD
CHECKED K. KERN
SHEET 111 OF 167