







DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS		EXISTING SIGNS				EXIST POST		NUMBER OF NEW POSTS	SQUARE STEEL (IN)			TUBULAR STEEL Ø (IN)				SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL LOCATION				
								"A"	"B"	RETAIN	SALVAGE FROM	SALVAGE TO	REMOVE	RETAIN	REMOVE		1.75	2.00	2.50	FOUNDATION	3.00	3.50	4.00			5.00	SHSM	PROJECT SHEET #	STANDARD SHEET #	
																	(LB / FT)				(LB / FT)									
<b>SOUTH HERO US-2 EB</b>							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																"SHSM"-STANDARD HIGHWAY SIGNS AND MARKINGS							
		A	W11-2	30	30	FYG		6.25							1	16.00	X								RETAIN FLASHING BEACON SIGN	X				
		A	W7-3aP	24	18	FYG	 04/21/15	3.00																		X				
EB	5.049	A	VW-205	30	30		WATCH FOR TURNING VEHICLES			1				X																
EB	5.088	A	W7-3A	24	18							1		X																
		A	W8-5	30	30							1						17.75												
		A	W8-5	30	30		 11/20/14	6.25							1			X								X				
		A	W8-5aP	24	12		 ICE NEXT 2 MILES	2.00																						
		A	W7-3aP	24	18			3.00																		X				
EB	5.135	A	R2-1	24	30							1		X				14.00												
		A	R2-1	24	30			5.00							1			X								X				
EB	5.271	A	R2-1	24	30							1		X				14.25												
		A	R2-1	24	30			5.00																		X				
EB	5.381	A	UNK.	UNK.	UNK.		LAKE CHAMPLAIN			1				X																
EB	5.413	A	R2-1	24	30							1		X																
		A	R3-9cP	30	12	BLK/ WHT		2.50							1			X								X				
<b>SIGN SUMMARY SHEET</b>							<b>SHEET TOTALS</b>	33.00	0.00	2	0	0	5	0	0	4	79.00			0	0.0	0.0	0.0	0.0	PROJECT NAME: ALBURGH-COLCHESTER PROJECT NUMBER: STPG SIGN(45)					
							SF	SF	EA	EA	EA	EA	EA	EA	EA	FT	EA	LB	LB	LB	LB	FILE NAME: 7 SOUTH HERO US2 EB TSS.xlt PLOT DATE: 3/14/2014 PROJECT MANAGER: D. BRYANT DRAWN BY: J. BLANCHARD DESIGNED BY: B. TOOTHAKER CHECKED: K. KERN SOUTH HERO EB SHEET 10 SHEET 116 OF 167								
VERMONT AGENCY OF TRANSPORTATION							<b>TOWN DIRECTIONAL TOTALS</b>	257.0	0.0	48	9	9	57	0	0	29	435.0	0		0.0										