DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB / FT) 1.88	SQUARE STEEL (IN) 2.00 (LB / FT) 2.42	SQUARE STEEL (IN) 2.50 (LB / FT) 3.35	TUBULAR STEEL Ø (IN) FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB / FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL LOCATION SHSM	SIGN DETAIL LOCATION PROJECT SHEET #	SIGN DETAIL LOCATION STANDARD SHEET #
SOUTH HERO US-2 EB							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																			"SHSM"-STANDARD HIGHWAY SIGNS AND MARKINGS			
		A	R8-3	24	24		BEGIN R 11/19/14	4.00																			X		
		A	R2-1	24	30		SPEED LIMIT 50	5.00																			X		
EB	5.429	A	VR-644P	24	12		BEGIN PARKING 11/19/14						1		X														
		A	R8-3A	24	24		NO PARKING SYMBOL						1																
EB	5.497	A	R8-3A	24	24								1		X														
		A	R8-3	24	24		R 11/19/14	4.00								1		13.75 X									X		
EB	5.628	A	R8-3	24	24		R 11/19/14	4.00								1		13.75 X								INSTALL 700 FT WEST OF PREVIOUS SIGN	X		
EB	5.759	A	R8-3A	24	24		11/19/14						1	X															
		A	R8-3	24	24		R	4.00																			X		
							SHEET TOTALS	21.00	0.00	0	0	0	4	0	0	2		27.50 ~~30.0~~		0	0.0	0.0	0.0	0.0					
								SF	SF	EA	EA	EA	EA	EA	EA	EA		FT		EA	LB	LB	LB	LB					
							TOWN DIRECTIONAL TOTALS	365.50 ~~257.0~~	0.0	48	9	9	71 ~~57~~	0	0	29		793.00 ~~435.0~~		0	0.0								

SIGN SUMMARY SHEET

VERMONT AGENCY OF TRANSPORTATION

PROJECT NAME: ALBURGH-COLCHESTER
PROJECT NUMBER: STPG SIGN(45)

FILE NAME: 7 SOUTH HERO US2 EB TSS.xls
PROJECT MANAGER: D. BRYANT
DESIGNED BY: B. TOOTHAKER
SOUTH HERO EB SHEET 11

PLOT DATE: 3/14/2014
DRAWN BY: J. BLANCHARD
CHECKED: K. KERN
SHEET 117 OF 167