DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB/FT) 1.88	SQUARE STEEL (IN) 2.00 (LB/FT) 2.42	SQUARE STEEL (IN) 2.50 (LB/FT) 3.35	TUBULAR STEEL Ø (IN) FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB/FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB/FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB/FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB/FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL LOCATION SHSM	SIGN DETAIL LOCATION PROJECT SHEET #	SIGN DETAIL LOCATION STANDARD SHEET #
SOUTH HERO US-2 WB							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																				"SHSM"-STANDARD HIGHWAY SIGNS AND MARKINGS			
WB	4.821	F	W16-1	18	18								1		X														
		F	W11-1	24	24								1																
		F	VD-503	12	18		CHAMPLAIN BIKEWAY						1																
		F	M6-1	12	9		GREEN ARROW						1																
		F	W11-1	30	30		12/02/14	6.25								1			16.50 X								X		
		F	W16-1P	18	24		12/02/14	3.00																			X		
WB	4.766	F	R4-6	24	30		TRUCK LANE 500 FEET			1				X															
WB	4.738	F	VR-921L	30	30		LEFT "ONLY"/THRU			1				X															
WB	4.721	F	R3-7L	30	30		LEFT LANE MUST TURN LEFT			1				X															
WB	4.656	F	R4-3	24	30		SLOWER TRAFFIC KEEP RIGHT			1				X															
WB	4.618	F	W11-3	30	30		11/20/14	6.25								1		16.25 X									INSTALL 200 FT WEST OF SLOWER TRAFFIC KEEP RIGHT SIGN	X		
		F	W7-3aP	24	18			3.00																				X		
WB	4.368	F	W16-1	18	18		SHARE THE ROAD			1				X															
		F	W11-1	24	24		BICYCLE SYMBOL			1																			
WB	4.225	F	W2-2R	36	36		RIGHT SIDE ROAD			1				X															
							SHEET TOTALS	18.50	0.00	7	0	0	4	0	0	2		32.75 ~~30.0~~		0	0.0	0.0	0.0	0.0					
								SF	SF	EA	EA	EA	EA	EA	EA	EA		FT		EA	LB	LB	LB	LB					
							TOWN DIRECTIONAL TOTALS	317.9	0.0	56	1	1	56	0	0	39		585.0		0		0.0							

SIGN SUMMARY SHEET

VERMONT AGENCY OF TRANSPORTATION

PROJECT NAME: ALBURGH-COLCHESTER
PROJECT NUMBER: STPG SIGN(45)

FILE NAME: 8 SOUTH HERO US2 WB TSS.x | PLOT DATE: 3/14/2014
PROJECT MANAGER: D. BRYANT | DRAWN BY: J. BLANCHARD
DESIGNED BY: B. TOOTHAKER | CHECKED K. KERN
SOUTH HERO WB SHEET 3 | SHEET 120 OF 167