DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB/FT) 1.88	SQUARE STEEL (IN) 2.00 (LB/FT) 2.42	SQUARE STEEL (IN) 2.50 (LB/FT) 3.35	TUBULAR STEEL Ø (IN) FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB/FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB/FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB/FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB/FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL LOCATION SHSM	SIGN DETAIL LOCATION PROJECT SHEET #	SIGN DETAIL LOCATION STANDARD SHEET #
SOUTH HERO US-2 WB							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																				"SHSM"-STANDARD HIGHWAY SIGNS AND MARKINGS			
		F	W16-8A	36	12		KIBBE POINT RD			1																			
WB	4.180	F	VD-062B	72	16		BUSINESS SIGN			1				X															
		F	VD-062B	72	16		BUSINESS SIGN			1																			
WB	4.128	F	W4-2R	36	36		RIGHT LANE REDUCTION			1				X															
WB	4.066	G	VR-017	24	30		11/20/14						1		X			13.75											
		G	VR-017	24	30		LEGAL LOAD LIMIT 24,000 POUNDS	5.00								1		X									KIBBE POINT RD (TH-12)		10	
WB	4.057	H	R1-1	30	30								1		X			13.75											
		H	R1-1	30	30		STOP 11/20/14	6.25								1		X									KIBBE POINT RD (TH-12)	X		
WB	4.057	E/F	D3-1	60	12		Kibbe Point Rd 11/20/14	5.00								2		11.25 X 11.25									KIBBE POINT RD (TH-12); FIELD LOCATE FOR VISIBILITY FROM ROUTE 2		14	
WB	3.992	F	UNK.	UNK.	UNK.		TRUCK LANE ENDS			1				X															
WB	3.623	F	VD-062AS	72	16		BUSINESS SIGN			1				X															
WB	3.447	F	W3-5	36	36		SPEED REDUCTION SPEED LIMIT 40						1		X															
WB	3.410	F	VD-062B	72	16		BUSINESS SIGN			1				X															
		F	VD-062B	72	16		BUSINESS SIGN			1																			
		F	VD-062B	72	16		BUSINESS SIGN			1																			
SIGN SUMMARY SHEET							SHEET TOTALS	16.25	0.00	9	0	0	3	0	0	4		~~60.0~~ 50.00		0	0.0	0.0	0.0	0.0					
								SF	SF	EA	EA	EA	EA	EA	EA	EA		FT		EA	LB	LB	LB	LB					
VERMONT AGENCY OF TRANSPORTATION							TOWN DIRECTIONAL TOTALS	317.9	0.0	56	1	1	56	0	0	39		585.0		0		0.0							

PROJECT NAME: ALBURGH-COLCHESTER
PROJECT NUMBER: STPG SIGN(45)
FILE NAME: 8 SOUTH HERO US2 WB TSS.x | PLOT DATE: 3/14/2014
PROJECT MANAGER: D. BRYANT | DRAWN BY: J. BLANCHARD
DESIGNED BY: B. TOOTHAKER | CHECKED K. KERN
SOUTH HERO WB SHEET 4 | SHEET 121 OF 167