DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB / FT) 1.88	SQUARE STEEL (IN) 2.00 (LB / FT) 2.42	SQUARE STEEL (IN) 2.50 (LB / FT) 3.35	TUBULAR STEEL Ø (IN) FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB / FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL LOCATION SHSM	SIGN DETAIL LOCATION PROJECT SHEET #	SIGN DETAIL LOCATION STANDARD SHEET #
SOUTH HERO US-2 WB							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																			"SHSM"-STANDARD HIGHWAY SIGNS AND MARKINGS			
WB	2.991	G	R7-1	24	30								1	X															
		G	R7-1	24	30		NO PARKING ANY TIME ← 11/20/14	5.00																			X		
WB	2.979	G	R7-1	24	30								1	X															
		G	R7-1	24	30		NO PARKING ANY TIME → 11/20/14	5.00																		REQUIRES VEGETATION CLEARING	X		
WB	2.957	F	UNK.	UNK.	UNK.		EMPTY POST IN THIS LOCATION 11/20/14								X														
		F	R2-1	24	30		SPEED LIMIT 35	5.00								1		12.25 X										X		
WB	2.929	F	M3-4	24	12	BLK/ WHT	WEST 11/20/14	2.00								1		X 13.25									INSTALL 150 FT WEST OF SPEED LIMIT SIGN	X		
		F	M1-4	24	24	BLK/ WHT	2	4.00																				X		
WB	2.861	F	VD-062B	72	16		BUSINESS SIGN			1				X															
WB	2.598	F	R2-1	24	30								1		X														
		F	R2-1	24	30		SPEED LIMIT 45 11/20/14	5.00								1		13.50 X										X		
WB	2.200	F	W2-2ML	30	30								1		X														
		F	VW-092	30	30		11/20/14						1						13.50											
		F	W2-2L	30	30		12/02/14	6.25								1			X								INSTALL 250 FT EAST OF INTERSECTION	X		
		F	VW-092	30	24		UNSAFE TO PASS 12/02/14	5.00																				NEED INFO		
							SHEET TOTALS	37.25	0.00	1	0	0	5	0	0	4		52.50 ~~60.0~~		0	0.0	0.0	0.0	0.0					
								SF	SF	EA	EA	EA	EA	EA	EA	EA		FT		EA	LB	LB	LB	LB					
							TOWN DIRECTIONAL TOTALS	317.9	0.0	56	1	1	56	0	0	39		585.0		0		0.0							

SIGN SUMMARY SHEET

VERMONT AGENCY OF TRANSPORTATION

PROJECT NAME: ALBURGH-COLCHESTER
PROJECT NUMBER: STPG SIGN(45)

FILE NAME: 8 SOUTH HERO US2 WB TSS.xl
PROJECT MANAGER: D. BRYANT
DESIGNED BY: B. TOOTHAKER
SOUTH HERO WB SHEET 7

PLOT DATE: 3/14/2014
DRAWN BY: J. BLANCHARD
CHECKED K. KERN
SHEET 124 OF 167