DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB/FT) 1.88	SQUARE STEEL (IN) 2.00 (LB/FT) 2.42	SQUARE STEEL (IN) 2.50 (LB/FT) 3.35	TUBULAR STEEL Ø (IN) FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB/FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB/FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB/FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB/FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL LOCATION SHSM	SIGN DETAIL LOCATION PROJECT SHEET #	SIGN DETAIL LOCATION STANDARD SHEET #
SOUTH HERO US-2 WB							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																			"SHSM"-STANDARD HIGHWAY SIGNS AND MARKINGS			
WB	1.477	H	R1-1	30	30								1		X														
		H	R1-1	30	30		STOP 11/21/14	6.25								1		14.00 X								KEELER BAY RD (TH-9); MOUNT IN CENTER ISLAND; REQUIRES VEGETATION CLEARING	X		
WB	1.390	F	VD-062AS	72	16		BUSINESS SIGN			1				X															
		F	VD-062AL	72	16		BUSINESS SIGN			1																			
WB	1.367	F	R2-1	24	30								1	~~X~~				14.00											
		F	R2-1	24	30		SPEED LIMIT 35 11/21/14	5.00																				X		
WB	1.285	F	VW-205	30	30		WATCH FOR TURNING VEHICLES			1				X															
WB	1.246	F	M2-1	21	15		JCT STATE			1				X															
		F	M1-5	30	24		VERMONT 314			1																			
WB	1.222	F	D1-1A	72	12		^UP CANADA 26			1				X															
		F	D1-1A	72	12		^UP ROUSE'S POINT NY 28			1																			
		F	VD1-1M	72	12		<--- NY STATE VIA FERRY 2			1																			
		F	VD1-1G	72	12		<--- L CHAMPLAIN ISLANDS			1																			
WB	1.206	F	VR-731	24	12		AT INTERSECTIONS			1				X															
		F	VW16-18P	24	12		STATE LAW PLAQUE			1																			
							SHEET TOTALS	11.25	0.00	11	0	0	2	0	0	1		~~15.0~~ 28.00		0	0.0	0.0	0.0	0.0					
								SF	SF	EA	EA	EA	EA	EA	EA	EA		FT		EA	LB	LB	LB	LB					
							TOWN DIRECTIONAL TOTALS	317.9	0.0	56	1	1	56	0	0	39		585.0		0		0.0							

SIGN SUMMARY SHEET

VERMONT AGENCY OF TRANSPORTATION

PROJECT NAME: ALBURGH-COLCHESTER
PROJECT NUMBER: STPG SIGN(45)
FILE NAME: 8 SOUTH HERO US2 WB TSS.xl PLOT DATE: 3/14/2014
PROJECT MANAGER: D. BRYANT DRAWN BY: J. BLANCHARD
DESIGNED BY: B. TOOTHAKER CHECKED K. KERN
SOUTH HERO WB SHEET 10 SHEET 127 OF 167