DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS		EXISTING SIGNS				EXIST POST		NUMBER OF NEW POSTS	SQUARE STEEL (IN)			TUBULAR STEEL Ø (IN)				SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL LOCATION		
								"A"	"B"	RETAIN	SALVAGE FROM	SALVAGE TO	REMOVE	RETAIN	REMOVE		1.75 (LB / FT) 1.88	2.00 (LB / FT) 2.42	2.50 (LB / FT) 3.35	FOUNDATION	3.00 (LB / FT) 7.60	3.50 (LB / FT) 9.00	4.00 (LB / FT) 10.80	5.00 (LB / FT) 14.60			SHSM	PROJECT SHEET #	STANDARD SHEET #
SOUTH HERO US-2 WB							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																		"SHSM"-STANDARD HIGHWAY SIGNS AND MARKINGS			
		F	R4-18	24	30		DO NOT PASS ON SHOULDER			1																		
WB	1.177	F	M3-1	24	12		NORTH STATE			1				X														
		F	M3-4	24	12		WEST US			1																		
		F	M1-4	24	24		US 2			1																		
		F	M1-5	30	24		VERMONT 314			1																		
		F	M6-3	21	15		^UP ARROW US			1																		
		F	M6-1	21	15		<--- LEFT STATE			1																		
WB	1.155	G	W1-7	48	24		<===> DOUBLE ARROW			1				X														
WB	1.114	F	M1-4	24	24		US 2			1				X														
		F	M3-4	24	12		WEST US			1																		
WB	1.080	F	D1-1a	72	12		^UP CANADA 26			1				X														
		F	D1-1a	72	12		^UP GRAND ISLE 3			1																		
		F	D1-1a	72	12		^UP ALBURGH 24			1																		
		F	D1-1a	72	12		^UP ROUSES POINT NY 28			1																		
WB	1.050	F	R2-1	24	30		SPEED LIMIT 40			1				X														
							SHEET TOTALS	0.00	0.00	15	0	0	0	0	0	0	0.0			0	0.0	0.0	0.0	0.0					
								SF	SF	EA	EA	EA	EA	EA	EA	EA	FT			EA	LB	LB	LB	LB					
							TOWN DIRECTIONAL TOTALS	317.9	0.0	56	1	1	56	0	0	39	585.0			0	0.0								

SIGN SUMMARY SHEET

VERMONT AGENCY OF TRANSPORTATION

PROJECT NAME: ALBURGH-COLCHESTER
PROJECT NUMBER: STPG SIGN(45)

FILE NAME: 8 SOUTH HERO US2 WB TSS.x| PLOT DATE: 3/14/2014
PROJECT MANAGER: D. BRYANT DRAWN BY: J. BLANCHARD
DESIGNED BY: B. TOOTHAKER CHECKED K. KERN
SOUTH HERO WB SHEET 11 SHEET 128 OF 167