DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB / FT) 1.88	SQUARE STEEL (IN) 2.00 (LB / FT) 2.42	SQUARE STEEL (IN) 2.50 (LB / FT) 3.35	TUBULAR STEEL Ø (IN) FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB / FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL LOCATION SHSM	SIGN DETAIL LOCATION PROJECT SHEET #	SIGN DETAIL LOCATION STANDARD SHEET #
MILTON US-2 WB							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																				"SHSM"-STANDARD HIGHWAY SIGNS AND MARKINGS			
WB	3.595	G	VR-017	24	30								1	X															
		G	VR-017	24	30		LEGAL LOAD LIMIT 24,000 POUNDS 11/11/14	5.00										14.00								RAINBOW PL (TH-104)		10	
WB	3.586	H	R1-1	30	30								1	X															
		E/F	D3-1	UNK.	UNK.		RAINBOW PL						1																
		H	R1-1	30	30		STOP 11/11/14	6.25																			RAINBOW PL (TH-104)	X		
WB	3.586	E/F	D3-1	42	12		Rainbow Pl 11/11/14	3.50								1		10.00 X									RAINBOW PL (TH-104); FIELD LOCATE FOR VISIBILITY FROM ROUTE 2		14	
WB	3.550	F	D11-1	24	18		11/11/14						1	X															
		F	D11-1	24	18		BIKE ROUTE	3.00																				X		
WB	3.500	F	W11-3A	30	30								1	X				15.00											
		F	W11-3	48	48			16.00																				X		
		F	W7-3aP	24	18		NEXT 1 MILE	3.00																				X		
WB	3.448	F	VR-428	24	30		ALL TURNS RIGHT LANE 11/11/14						1		X			13.25 13.75									SLIP BASES			
		F	R3-23	60	36		ALL TURNS FROM RIGHT LANE	15.00								2		X										X		
WB	3.410	F	D1-1M	72	12		BEAR TRAP RD ---> (45 DEG) 11/11/14						1		X			13.25 14.75												
		F	VD1-1	72	12		Bear Trap Rd Cub Rd	6.00								2		X											8	
							SHEET TOTALS	57.75	0.00	0	0	0	7	0	0	5		94.00 ~~75.0~~		0	0.0	0.0	0.0	0.0					
								SF	SF	EA	EA	EA	EA	EA	EA	EA		FT		EA	LB	LB	LB	LB					
							TOWN DIRECTIONAL TOTALS	317.3	0.0	4	0	0	46	0	0	24		360.0		0	0.0								

SIGN SUMMARY SHEET

VERMONT AGENCY OF TRANSPORTATION

PROJECT NAME: ALBURGH-COLCHESTER
PROJECT NUMBER: STPG SIGN(45)

FILE NAME: 10 MILTON US2 WB TSS.xls
PROJECT MANAGER: D. BRYANT
DESIGNED BY: B. TOOTHAKER
MILTON WB SHEET 1

PLOT DATE: 3/14/2014
DRAWN BY: J. BLANCHARD
CHECKED K. KERN
SHEET 137 OF 167