DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB/FT) 1.88	SQUARE STEEL (IN) 2.00 (LB/FT) 2.42	SQUARE STEEL (IN) 2.50 (LB/FT) 3.35	TUBULAR STEEL Ø (IN) FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB/FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB/FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB/FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB/FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL LOCATION SHSM	SIGN DETAIL LOCATION PROJECT SHEET #	SIGN DETAIL LOCATION STANDARD SHEET #
COLCHESTER US-2 EB							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																			"SHSM"-STANDARD HIGHWAY SIGNS AND MARKINGS			
EB	0.000	C	VD-024	60	7.5								1 I	X															
		C	VD-024	72	10		Colchester | Milton	5.00					I					I7.75										7	
		C	VD-700	6	10		0020 0405 0000 | 0200 0410 0369	0.42																					E-138
		C	VD-700	6	10		II/04/14	0.42																					E-138
EB	0.058	A	D1-11	24	18		BIKE ROUTE SYMBOL II/13/14						1 I		X				I7.75 I8.00										
		A	W11-1	48	48			16.00								2			X								SLIP BASES	X		
		A	W11-15P	36	30		TRAIL X-ING	7.50																				X		
EB	0.095	F	M4-6	24	12	WHT/ GRN	END II/04/14	2.00								1		X I3.00									INSTALL 200 FT EAST OF BIKE ROUTE SYMBOL	X		
		F	D11-1	24	18		BIKE ROUTE	3.00																				X		
EB	0.119	A	R2-1	36	48		II/04/14						1	X				I6.00												
		A	R2-1	30	36		SPEED LIMIT 55	7.50																			0.148 SLIP BASES	X		
EB	0.166	A	VD-062B	72	16		BUSINESS SIGN II/03/14			1				X																
EB	0.198	A	VR-428	24	30		ALL TURNS RIGHT LANE II/03/14						1		X												SLIP BASES			
		A	UNK.	24	30		NO PARKING ALL TOWN HIGHWAYS NOV 15-MAR15 VEHICLES TOWED AT OWNER'S EXPENSE				~~1~~		1				I3.75 I4.25								SALVAGE SIGN AND RETURN TO TOWN			
		A	R3-23	60	36		ALL TURNS FROM RIGHT LANE	15.00					I			2		X												
SIGN SUMMARY SHEET							SHEET TOTALS	~~56.84~~ ~~50.83~~	0.00	1	1	0	~~9~~ ~~5~~	0	0	5		~~110.50~~ ~~75.0~~		0	0.0	0.0	0.0	0.0						
								SF	SF	EA	EA	EA	EA	EA	EA	EA		FT		EA	LB	LB	LB	LB					
VERMONT AGENCY OF TRANSPORTATION							TOWN DIRECTIONAL TOTALS	451.3	0.0	68	1	0	57	0	0	44		660.0		0	0.0								

PROJECT NAME: ALBURGH-COLCHESTER
PROJECT NUMBER: STPG SIGN(45)
FILE NAME: 11 COLCHESTER US2 EB TSS.; PLOT DATE: 3/14/2014
PROJECT MANAGER: D. BRYANT; DRAWN BY: J. BLANCHARD
DESIGNED BY: B. TOOTHAKER; CHECKED K. KERN
COLCHESTER EB SHEET 1; SHEET 144 OF 167