DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB/FT) 1.88	SQUARE STEEL (IN) 2.00 (LB/FT) 2.42	SQUARE STEEL (IN) 2.50 (LB/FT) 3.35	TUBULAR STEEL Ø (IN) FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB/FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB/FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB/FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB/FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL LOCATION SHSM	SIGN DETAIL LOCATION PROJECT SHEET #	SIGN DETAIL LOCATION STANDARD SHEET #
COLCHESTER US-2 EB							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																			"SHSM"-STANDARD HIGHWAY SIGNS AND MARKINGS			
		B	R5-1	30	30			6.25																		INSTALL ON REVERSE OF STOP SIGN	X		
EB	0.408	A	R3-3	48	48		NO TURNS 11/06/14	16.00								2		10.25 X 10.75								IN MEDIAN AT INTERSECTION OF ROUTE 2 AND CLAY POINT RD (TH-58)	X		
		B	R3-3	48	48		NO TURNS	16.00																			X		
EB	0.409	A	D3-1	UNK.	12		CLAY POINT RD 11/04/14						1		X											CLAY POINT RD (TH-58)			
EB	0.409	B	R5-1	30	30		11/04/14						1	X	I			12.25											
		A	R1-1	30	30		STOP	6.25																		IN MEDIAN AT INTERSECTION OF JUGHANDLE AND CLAY POINT RD (TH-58)	X		
		B	R5-1	30	30		DO NOT ENTER	6.25																		INSTALL ON REVERSE OF STOP SIGN	X		
EB	0.409	C	VR-017	24	30								1	~~X~~	I			12.25											
		C	VR-017	24	30		LEGAL LOAD LIMIT 24,000 POUNDS 11/04/14	5.00																		CLAY POINT RD (TH-58); INSTALL WEST OF JUGHANDLE		10	
EB	0.416	D	R1-1	30	30		11/04/14						1	X	~~X~~														
		D	R1-1	30	30		STOP	6.25								~~1~~		~~X~~								CLAY POINT RD (TH-58)	X		
EB	0.417	A	W1-7	48	24		<===> 11/05/14						1		X			12.25 12.25											
		A	VD1-1	72	12		← Clay Point Rd →	6.00								2		X								CLAY POINT RD (TH-58); INSTALL CENTERED ACROSS FROM JUGHANDLE INTERSECTION		9	
EB	0.471	A	R8-7	30	24		11/13/14						1		X			15.00 15.50											
		A	R8-7	48	36		EMERGENCY STOPPING ONLY	12.00								2		X									X		
SIGN SUMMARY SHEET							SHEET TOTALS	80.00	0.00	0	0	0	6	0	0	7		~~100.50~~ ~~105.0~~		0	0.0	0.0	0.0	0.0					
								SF	SF	EA	EA	EA	EA	EA	EA	EA		FT		EA	LB	LB	LB	LB					
VERMONT AGENCY OF TRANSPORTATION							TOWN DIRECTIONAL TOTALS	451.3	0.0	68	1	0	57	0	0	44		660.0		0	0.0								

PROJECT NAME: **ALBURGH-COLCHESTER**
PROJECT NUMBER: **STPG SIGN(45)**
FILE NAME: **11 COLCHESTER US2 EB TSS.** PLOT DATE: **3/14/2014**
PROJECT MANAGER: **D. BRYANT** DRAWN BY: **J. BLANCHARD**
DESIGNED BY: **B. TOOTHAKER** CHECKED **K. KERN**
COLCHESTER EB SHEET 3 SHEET **146** OF **167**