DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB / FT) 1.88	SQUARE STEEL (IN) 2.00 (LB / FT) 2.42	SQUARE STEEL (IN) 2.50 (LB / FT) 3.35	TUBULAR STEEL Ø (IN) FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB / FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL LOCATION SHSM	SIGN DETAIL LOCATION PROJECT SHEET #	SIGN DETAIL LOCATION STANDARD SHEET #
COLCHESTER US-2 EB							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																			"SHSM"-STANDARD HIGHWAY SIGNS AND MARKINGS			
		A	M1-1	24	24		INTERSTATE 89			1																			
		A	M6-3	21	15		^UP ARROW INTERSTATE			1																			
		A	M3-2	24	12		EAST US			1																			
		A	M1-4	24	24		US 2			1																			
		A	M6-3	21	15		^UP ARROW US			1																			
		A	M3-3	24	12		SOUTH INTERSTATE			1																			
		A	M1-1	24	24		INTERSTATE 89			1																			
		A	M6-1	21	15		RIGHT ---> INTERSTATE			1																			
EB	1.806	A	W3-3	36	36		SIGNAL AHEAD SYMBOL	9.00		1				X															
EB	1.808	A	E6-1A	120	126		I89 SOUTH WINOOSKI BURLINGTON			1				X															
EB	1.852	A	W11-1	30	30			6.25								1	X ~~17.50~~									INSTALL 232 FT EAST OF LARGE INTERSTATE PANEL	X		
		A	W16-1P	18	24			3.00																			X		
EB	1.931	B	M3-3	24	12		SOUTH INTERSTATE			1				X															
		B	M1-1	24	24		INTERSTATE 89			1																			
		B	M6-1	21	15		<--- LEFT INTERSTATE			1																			
							SHEET TOTALS	~~18.25~~ 9.25 SF	0.00 SF	13 EA	0 EA	0 EA	0 EA	0 EA	0 EA	1 EA	~~17.50~~ 15.0 FT			0 EA	0.0 LB	0.0 LB	0.0 LB	0.0 LB				
							TOWN DIRECTIONAL TOTALS	451.3	0.0	68	1	0	57	0	0	44	660.0			0	0.0								

SIGN SUMMARY SHEET

VERMONT AGENCY OF TRANSPORTATION

PROJECT NAME: ALBURGH-COLCHESTER
PROJECT NUMBER: STPG SIGN(45)

FILE NAME: 11 COLCHESTER US2 EB TSS.; PLOT DATE: 3/14/2014
PROJECT MANAGER: D. BRYANT DRAWN BY: J. BLANCHARD
DESIGNED BY: B. TOOTHAKER CHECKED K. KERN
COLCHESTER EB SHEET 9 SHEET 152 OF 167