DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB / FT) 1.88	SQUARE STEEL (IN) 2.00 (LB / FT) 2.42	SQUARE STEEL (IN) 2.50 (LB / FT) 3.35	FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB / FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL LOCATION SHSM	SIGN DETAIL LOCATION PROJECT SHEET #	SIGN DETAIL LOCATION STANDARD SHEET #
COLCHESTER US-2 EB							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																			"SHSM"-STANDARD HIGHWAY SIGNS AND MARKINGS			
		A	M3-1	24	12		NORTH US			1																			
		A	M1-4	24	24		US-7			1																			
		A	M6-1	21	15		<-- LEFT ARROW US			1																			
		A	M3-2	24	12		EAST US			1																			
		A	M1-4	24	24		US-2			1																			
		A	M6-1	21	15		RIGHT ARROW -->			1																			
		A	M3-3	24	12		SOUTH US			1																			
		A	M1-4	24	24		US-7			1																			
		A	M6-1	21	15		RIGHT ARROW -->			1																			
							SHEET TOTALS	0.00	0.00	9	0	0	0	0	0	0		0.0		0	0.0	0.0	0.0	0.0					
								SF	SF	EA	EA	EA	EA	EA	EA	EA		FT		EA	LB	LB	LB	LB					
							TOWN DIRECTIONAL TOTALS	403.44 ~~451.3~~	0.0	68	1	0	65 ~~57~~	0	0	44		637.50 ~~660.0~~		0	0.0								

SIGN SUMMARY SHEET

VERMONT AGENCY OF TRANSPORTATION

PROJECT NAME: ALBURGH-COLCHESTER
PROJECT NUMBER: STPG SIGN(45)
FILE NAME: 11 COLCHESTER US2 EB TSS.
PROJECT MANAGER: D. BRYANT
DESIGNED BY: B. TOOTHAKER
COLCHESTER EB SHEET 13
PLOT DATE: 3/14/2014
DRAWN BY: J. BLANCHARD
CHECKED BY: K. KERN
SHEET 156 OF 167