DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS		EXISTING SIGNS				EXIST POST		NUMBER OF NEW POSTS	SQUARE STEEL (IN)			TUBULAR STEEL Ø (IN)				SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL LOCATION		
								"A"	"B"	RETAIN	SALVAGE FROM	SALVAGE TO	REMOVE	RETAIN	REMOVE		1.75 (LB / FT)	2.00 (LB / FT)	2.50 (LB / FT)	FOUNDATION	3.00 (LB / FT)	3.50 (LB / FT)	4.00 (LB / FT)	5.00 (LB / FT)			SHSM	PROJECT SHEET #	STANDARD SHEET #
COLCHESTER US-2 WB							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																		"SHSM"-STANDARD HIGHWAY SIGNS AND MARKINGS			
WB	2.183	K	R4-7	24	30		RIGHT BULLNOSE			1				X														
		J	OM1-1	18	18		YELLOW MARKER			1																		
		K	OM1-1	18	18		YELLOW MARKER			1																		
WB	2.167	F	M3-4	24	12		JCT INTERSTATE			1				X														
		F	M1-4	24	24		I-89			1																		
		F	M2-1	21	15		WEST STATE			1																		
		F	M1-1	24	24		US-2			1																		
WB	2.130	F	E6-1A	120	126		I89 NORTH ===> GEORGIA ST ALBANS MONTREAL			1				X														
WB	2.087	F	W4-1R	36	36		MERGE RIGHT SYMBOL			1				X														
WB	2.047	F	W16-1	18	18		SHARE THE ROAD			1				X														
		F	W11-1	24	24		BICYCLE SYMBOL			1																		
WB	2.03	F	M3-4	24	12		WEST US			1				X														
		F	M1-4	24	24		US 2			1																		
WB	1.974	F	VR-921L	30	30		LEFT "ONLY"/THRU			1				X														
WB	1.961	F	R3-7L	30	30								1	X														
							SHEET TOTALS	0.00	0.00	14	0	0	1	0	0	0	0.0			0	0.0	0.0	0.0	0.0					
								SF	SF	EA	EA	EA	EA	EA	EA	EA		FT		EA	LB	LB	LB	LB					
							TOWN DIRECTIONAL TOTALS	464.5	0.0	22	0	0	52	0	0	43	645.0			0	0.0								

SIGN SUMMARY SHEET

VERMONT AGENCY OF TRANSPORTATION

PROJECT NAME: ALBURGH-COLCHESTER
PROJECT NUMBER: STPG SIGN(45)

FILE NAME: 12 COLCHESTER US2 WB TSS PLOT DATE: 3/14/2014
PROJECT MANAGER: D. BRYANT DRAWN BY: J. BLANCHARD
DESIGNED BY: B. TOOTHAKER CHECKED K. KERN
COLCHESTER WB SHEET 1 SHEET 157 OF 167