DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB / FT) 1.88	SQUARE STEEL (IN) 2.00 (LB / FT) 2.42	SQUARE STEEL (IN) 2.50 (LB / FT) 3.35	TUBULAR STEEL Ø (IN) FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB / FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL LOCATION SHSM	SIGN DETAIL LOCATION PROJECT SHEET #	SIGN DETAIL LOCATION STANDARD SHEET #
COLCHESTER US-2 WB							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																			"SHSM"-STANDARD HIGHWAY SIGNS AND MARKINGS			
		F	D11-1	24	18								1																
		F	M4-14	24	12	WHT/ GRN	BEGIN	2.00										14.00									X		
		F	D11-1	24	18		BIKE ROUTE	3.00																			X		
WB	1.632	F	R2-1	36	48								1	X				14.00											
		F	R2-1	30	36		SPEED LIMIT 55	7.50																			X		
WB	1.330	F	VD-062AS	72	16		BUSINESS SIGN			1				X															
		F	VD-062AS	72	16		BUSINESS SIGN			1																			
WB	1.293	F	VR-428	24	30		ALL TURNS RIGHT LANE 10/31/14						1		X			13.25 14.25									SLIP BASES		
		F	R3-23	60	36		ALL TURNS FROM RIGHT LANE	15.00								2	X										X		
WB	1.236	F	D1-1M	72	12		10/31/14						1	X															
		F	VD1-1	72	12		Raymond Rd	6.00																				9	
WB	1.184	F	VR-903R	36	30		THRU/RIGHT ALL TURNS 10/31/14						1 1		X														
WB	1.139	F	VR-284	30	36		ALL TURNS ===> (45 DEG)						1 1		X			12.00 12.50											
		F	R3-24	72	18		ALL TURNS 11/13/14	9.00								2	X										X		
WB	1.069	F	VR-284	30	36		ALL TURNS ===> (45 DEG)						1 1		X														
SIGN SUMMARY SHEET							SHEET TOTALS	42.50	0.00	2	0	0	10 ~~7~~	0	0	4		50.00 ~~60.0~~		0	0.0	0.0	0.0	0.0					
								SF	SF	EA	EA	EA	EA	EA	EA	EA		FT		EA	LB	LB	LB	LB					
VERMONT AGENCY OF TRANSPORTATION							TOWN DIRECTIONAL TOTALS	464.5	0.0	22	0	0	52	0	0	43		645.0		0		0.0							

PROJECT NAME: ALBURGH-COLCHESTER
PROJECT NUMBER: STPG SIGN(45)
FILE NAME: 12 COLCHESTER US2 WB TSS PLOT DATE: 3/14/2014
PROJECT MANAGER: D. BRYANT DRAWN BY: J. BLANCHARD
DESIGNED BY: B. TOOTHAKER CHECKED K. KERN
COLCHESTER WB SHEET 5 SHEET 161 OF 167