DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB/FT) 1.88	SQUARE STEEL (IN) 2.00 (LB/FT) 2.42	SQUARE STEEL (IN) 2.50 (LB/FT) 3.35	TUBULAR STEEL Ø (IN) FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB/FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB/FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB/FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB/FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL LOCATION SHSM	SIGN DETAIL LOCATION PROJECT SHEET #	SIGN DETAIL LOCATION STANDARD SHEET #
COLCHESTER US-2 WB							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																				"SHSM"-STANDARD HIGHWAY SIGNS AND MARKINGS			
		F	R3-24	72	18		ALL TURNS ↗ 10/31/14	9.00					1			2	12.75 X 12.75											X		
WB	1.059	F	R3-2	24	24		NO LEFT TURN SYMBOL 10/31/14						1 1		X														
WB	1.048	E	R3-3	48	48		NO TURNS 11/06/14	16.00								2	10.50 X 11.25										INSTALL IN MEDIAN AT INTERSECTION OF RTE 2 AND RAYMOND RD (TH-40)	X		
		F	R3-3	48	48		NO TURNS	16.00																		SLIP BASES	X		
WB	1.048	E	R5-1	30	30								1 1		X														
		E	R5-1	30	30		DO NOT ENTER 10/31/14	6.25								1	12.75 X										IN MEDIAN AT INTERSECTION OF JUGHANDLE AND RAYMOND RD (TH-40)	X		
		F	R1-1	30	30		STOP	6.25																		INSTALL ON REVERSE OF STOP SIGN	X		
WB	1.048	F	R1-1	30	30								1	~~X~~															
		E	R5-1	30	30								1				10.25												
		E	R5-1	30	30		DO NOT ENTER 10/31/14	6.25																		EAST OF JUGHANDLE AT INTERSECTION WITH RAYMOND RD (TH-40)	X		
		F	R1-1	30	30		STOP	6.25																		INSTALL ON REVERSE OF STOP SIGN	X		
WB	1.046	G	VR-017	24	30								1		X														
		G	VR-017	24	30		LEGAL LOAD LIMIT 24,000 POUNDS 10/31/14	5.00									13.25 X										RAYMOND RD (TH-40); INSTALL EAST OF JUGHANDLE		10	
WB	1.038	F	W1-6	48	24		<===>						1		X		13.50 13.25												
		F	VD1-1	72	12		← Raymond Rd → 10/31/14	6.00								2	X										RAYMOND RD (TH-40); INSTALL CENTERED ACROSS FROM JUGHANDLE INTERSECTION		9	
SIGN SUMMARY SHEET							SHEET TOTALS	77.00	0.00	0	0	0	~~9~~ 6	0	0	8	~~110.25~~ 120.0			0	0.0	0.0	0.0	0.0					
								SF	SF	EA	EA	EA	EA	EA	EA	EA	FT			EA	LB	LB	LB	LB					
VERMONT AGENCY OF TRANSPORTATION							TOWN DIRECTIONAL TOTALS	464.5	0.0	22	0	0	52	0	0	43	645.0			0	0.0								

PROJECT NAME: ALBURGH-COLCHESTER
PROJECT NUMBER: STPG SIGN(45)
FILE NAME: 12 COLCHESTER US2 WB TSS PLOT DATE: 3/14/2014
PROJECT MANAGER: D. BRYANT DRAWN BY: J. BLANCHARD
DESIGNED BY: B. TOOTHAKER CHECKED K. KERN
COLCHESTER WB SHEET 6 SHEET 162 OF 167